

CONCRETE AND CONSTRUCTIONAL ENGINEERING

INCLUDING PRESTRESSED CONCRETE

JUNE, 1954.



Vol. XLIX, No. 6

FORTY-NINTH YEAR OF PUBLICATION

PRICE 1s. 6d.

ANNUAL SUBSCRIPTION 18s. POST FREE. \$3.00 in Canada and U.S.A.

LEADING CONTENTS

	PAGE
The Quality of Concrete	179
Reinforced Concrete Arch Bridge in Brazil. <i>By E. Harold Sidwell</i>	181
Book Reviews	188
German Recommendations for Prestressed Concrete	189
Thickened Slabs in Place of Beams	193
Partially-prestressed Helical Stairs	197
Strengthening the Foundations of the Guildhall, London	199
Corrosion of Steel in Prestressed Concrete	201
Plastic Moulds for Precast Slabs	202

No. 559.

ISSUED MONTHLY

Registered for
Canadian Magazine Post

BOOKS ON CONCRETE For catalogue of "Concrete Series" books on concrete and allied subjects, send a postcard to:
CONCRETE PUBLICATIONS LTD., 14 DARTMOUTH ST., LONDON, S.W.1

A NEW "CONCRETE SERIES" BOOK

"THEORY AND PRACTICE OF STRUCTURAL DESIGN APPLIED TO REINFORCED CONCRETE"

By B. ERIKSEN

402 pages. 252 illustrations. 38 tables. Price 25s. ; 26s. by post.
(\$5.50 in Canada and U.S.A.)

★ A new book on the Theory of Structures. The methods are applicable to all materials, but particular regard is given to reinforced concrete. A complete treatise from the first laws of statics to the analysis of indeterminate structures. Many worked examples. Gives all the information necessary to design in reinforced concrete.

★ A feature of the book is the detailed treatment of the fixed-point method of analysis, which is applied to continuous beams and frames. A semi-graphical application of this method enables bending moments on rigid frames to be rapidly calculated with an accuracy sufficient for practical purposes. Other methods of analysis of statically-indeterminate structures with members of constant or varying moment of inertia are given. Construction of influence lines and the calculation of bending moments due to moving loads. Complete calculations for the analysis of a bridge with beams of varying depth supported on piled foundations.

CONCRETE PUBLICATIONS LIMITED

14 DARTMOUTH STREET, LONDON, S.W.1

Burton's

(SAFETY LOCK—UNIQUE FEATURE)

TUBULAR STEEL PROPS

(ADJUSTABLE)

For Supporting Temporary Floor Shuttering

Burton's Adjustable Tubular Steel Props

for the above and many other purposes, are much preferred by the men who erect them to the old-fashioned Timber Props. They can be erected by one man in a few minutes and positively adjusted and safely locked in position, thus avoiding any possibility of being accidentally or maliciously tampered with.

Manufactured in our own most modern and up-to-date works at Old Hill, Staffs.

No spanner, jack, or tommy bar necessary; simply lift inner tube, insert peg, and tighten up.

No loose parts to lose, and easily transported.

BURTON'S ADJUSTABLE TUBULAR STEEL BEAM PROPS

are provided, as illustrated, with a braced head for supporting temporary shuttering to R.S.J. casings and reinforced concrete beams, &c.



Size No.	HEIGHT		Approx. Weight each in Lbs.
	Fully Closed	Fully Extended	
1.	5 ft. 7 in.	9 ft. 10 in.	50
2.	6 ft. 7 in.	10 ft. 10 in.	54
3.	8 ft. 2½ in.	12 ft. 5½ in.	58
4.	11 ft. 0 in.	16 ft. 0 in.	72

Head Fittings to suit any Special Job, designed for use with BURTON'S PROPS.

Burton's Patent Solid Dropforged Steel Scaffolding Fittings

THE LONDON & MIDLAND STEEL SCAFFOLDING CO., LTD.

ST. LUKE'S WORKS, OLD HILL, STAFFORDSHIRE

Telegrams: DUBELGRIP, CRADLEY HEATH.

Telephone: CRADLEY HEATH 6237/8

London Offices: 6 LYGON PLACE, S.W.1

Telephone: SLOane 7291-2-3.

Telegrams: DUBELGRIP, SOWEST, LONDON


POWER BAR BENDERS

FOR ALL SIZES OF REINFORCING BARS


STANDARD PRODUCTION MODELS

The ARD. 50 MODEL—as illustrated on right—has a capacity for cold bending Mild Steel Bars up to 2" dia. and incorporates a second Bending Head to give high-rate bending for small diameter bars.

The RAS. 40 MODEL shown below is a single disc machine of exceptional performance. With a capacity for 1½" dia. bars, it bends at highest practical rate—e.g. a full hook takes only 3 seconds bending time.



*Ensure accuracy, economy
& simplicity of operation*



INTERESTING FEATURES

Either of the Models illustrated can be supplied motorised or engine driven.

Standard Accessories supplied include all necessary Formers and Bending Pins, a special Backrest for simultaneous bending of a number of small diameter bars, and Accessories for forming right-angle loops in one operation.

Special Safety Device incorporated to prevent damage to mechanism if overloaded.

The desired Bending Angle may be set mathematically, and this is of great assistance in Repetition Bending.

CEMENT & STEEL LTD.

SECOND AVENUE

CHATHAM

KENT

Telephone : Chatham 45580

Telegrams and Cables : Cembelgi, Chatham


UNI-TUBE the pliable steel tube for forming all ducts in concrete ..

KOPEX PATENT PROCESS

It is supplied in $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", $1\frac{1}{2}$ ", 1 $\frac{3}{4}$ ", 1 $\frac{1}{2}$ ", and 2" diameters (or larger sizes if required up to 8" diameter) and in lengths as required.

1. External ribs
2. Smooth bore
3. Easily bent by hand
4. Stays put
5. Extremely light weight
6. No distortion of bore.
7. No frayed or loose ends

As approved and supplied
for the
Lee-McCall, Freyssinet,
and Gifford-Udall systems



DUCTS FOR PRESTRESSING CABLES

Labour saving . . . easy to install . . . outer corrugation gives a perfect bond to the surrounding concrete . . . the inside of the tube is smooth to facilitate the passage of bars or cables and allows free flow of grout. These are some of the advantages of the new Uni-Tube which make it the ideal and economical method of forming cable-ducts, with unskilled labour and without any special apparatus for the most intricate prestressed concrete design. Coupling covers for use with this tubing for McAlloy also supplied.

DUCTS FOR PERMANENT INSTALLATIONS

Uni-Tube is also being widely used as the best and most economical means of providing a duct in concrete, which has a smooth bore and is free of obstacles, through which electrical wiring, piping, etc., can be passed with speed and a saving in labour.

UNI-TUBES, LTD. 9 SOUTH MOLTON STREET, W.1. Telephone: MAYFAIR 7015

WORKS: ALPHA STREET, SLOUGH

Telephone: SLOUGH 24606



HUMDINGER

The Higher Frequency Vibrator
with the
**SLOW SPEED
DRIVE**




★ for **FASTER PLACING**
★ **BETTER CONCRETE**
★ **LOWER COSTS**

"Humdinger" frequencies of 10/12,000 VPM can deal more efficiently with the harshest "mixes". Equally important is the established fact that the flexible drives keep running week after week. That is why so many leading contractors have changed to this new Vibrator—it reduces hold-ups, in addition assures lower vibrating costs on every cubic yard placed.

Please write for leaflet.

Now available for Trial—Hire or Sale.



PETROL OR ELECTRIC



ACE Machinery Ltd., Vibrator Department, Porden Rd., Brixton, London, S.W.2. BR1xton 3293 (9 lines)

ABELSON

POURING SKIPS

for CONCRETE, CEMENT and AGGREGATES




Chains to suit—
4 leg 5/16" M.S.
Weight 18 lbs or 25 lbs.
S.W.L. 16 cwt & 30 cwt.



OTHER SIZES
AND TYPES
MADE TO ORDER

SEE OUR STAND
NO. 2, M. O. W.
BUILDING PLANT
EXHIBITION
HILLS MEADOW
READING
JUNE 24-30

SIZE	CAPACITY CU. FT.		
	18	14	9
Height 'A'	3' 9"	Bottom 3' 6" Side 3' 8"	3' 3"
Length 'B'	3' 10"	3' 3"	3' 3"
Width 'C'	3' 10"	3' 3"	2' 5"
Weight 'D'	3½ cwt.	3 cwt.	2 cwt.
Overall Height inc. Chains 'E'	7' 6"	7' 4"	7' 2"
Construction 'H'	1/8" M.S. Plate 2" x 3/16" A/Iron		
Stand 'J1' x 'J2'	2" A/Iron 3' 0" x 2' 8"	2" A/Iron 2' 8" x 2' 4"	2" A/Iron 3' 0" x 2' 2"
'F1' x 'F2'	Discharge Gate		
Bottom	1' 10" x 10"	1' 6" x 11"	1' 5" x 11"
Side	1' 10" x 11"	1' 6" x 8"	1' 6" x 8"
'K'	Price Ex-Works C.W. Chains		
Bottom	£50-0-0	£47-0-0	£35-0-0
Side	£55-0-0	£50-0-0	£37-0-0



Please write to Dept. C.S.1:

ABELSON & CO. (Engineers) LTD., SHELDON, BIRMINGHAM, 26

Phone: Sheldon 2424 (10 lines)

Grams: Abelson, Birmingham

London Office
70 VICTORIA STREET, LONDON, S.W.1
Telephone: TATe Gallery 9444

Manchester Office
100 OXFORD ROAD, MANCHESTER, 13
Telephone: Manchester ARDwick 1328

MILLPROPS

make it
a *FAST*
job



- Robust and dependable
- High Tensile Steel Pin
- Adjusted by Nut and Handle
- In three sizes Standard and Beam Types
- Individually tested to Safe Load

TYPE	HEIGHT		APPROX. WEIGHT IN LBS.	SAFE LOAD IN TONS	
	FULLY CLOSED	FULLY EXTENDED		FULLY CLOSED	FULLY EXTENDED
A	5 ft. 7 ins.	9 ft. 9 ins.	50	5.00	4.12
B	8 ft. 1 in.	12 ft. 3 ins.	58	5.00	3.57
C	10 ft. 7 ins.	14 ft. 9 ins.	72	5.00	2.17


AVAILABLE FOR
SALE OR HIRE
IMMEDIATE
DELIVERY

MILLS SCAFFOLD CO. LTD.

(A subsidiary of Guest, Keen & Nettlefolds, Ltd.)

Head Office: TRUSSLEY WORKS, HAMMERSMITH GROVE, LONDON, W.6 • Telephone: RIVerside 5026/9

Agents and Depots: BELFAST • BIRMINGHAM • BOURNEMOUTH • BRIGHTON • BRISTOL • CANTERBURY • CARDIFF
COVENTRY • CROYDON • DUBLIN • GLASGOW • HULL • ILFORD • LIVERPOOL • LOWESTOFT • MANCHESTER
NEWCASTLE • NORWICH • PLYMOUTH • PORTSMOUTH • READING • SHIPLEY • SOUTHAMPTON • SWANSEA • YARMOUTH




COAL BLENDING
BUNKER

FOR
WOODALL - DUCKHAM CONSTRUCTION COMPANY LTD
AT JOHN LYŠAGHT'S SCUNTHORPE WORKS LIMITED

PETER LIND & CO LTD

ROMNEY HOUSE, TUFTON STREET, LONDON, S.W.1

TELEPHONE ABBEY 7361



STAYTHORPE POWER STATION

By courtesy of The British Electricity Authority

Engineers and Main Contractors :

Messrs. Balfour, Beatty & Co. Ltd.

Consulting Architects :

Messrs. Cecil Howitt & Partners

FRANKIPILES

THE FRANKI COMPRESSED PILE COMPANY LIMITED

39 VICTORIA STREET LONDON S.W.1

Telephone : Abbey 6006-9 • Telegrams : Frankipile, Sowest London

And in AUSTRALASIA • B. W. INDIES • RHODESIA • S. AFRICA



FRANKI (Driven) Piles

FORUM (Bored) Piles

MIGA (Jacked) Piles

R. C. Foundations



This one-inch head pneumatic immersion vibrator will solve all problems in obtaining efficient vibration of thin concrete members and concrete which is congested with reinforcement or prestressing wire. The vibrator will give equal satisfaction for general concrete work, as the 1" dia. head can be interchanged in a few minutes for a more powerful 1½" or 2½" dia. head. The weight of the type AS 30 is only 15 lb. and its frequency is 12,000 r.p.m.

NEEDLE VIBRATOR

**with one-inch
diameter head
for concrete
which is congested
with reinforcement
or prestressing wire**


COMPACTORS ENGINEERING LTD.

65 EFFRA ROAD,

LONDON, S.W.2

TELEPHONE: BRIXTON 4081-3

"CAPCO" H. F. VIBRATOR



for compacting mortar cubes
for Compression Test B.S.
12/1947, B.S. 915/1947,
B.S. 146/1947, B.S. 1370/
1947. New type automa-
tic control—optional. The
vibrator illustrated in the
B.S. was built in our works.

The "CAPCO" range of con-
crete testing apparatus also
includes Cube Moulds; Slump
Cones; Tensile, Vicat, and Cylind-
rical Moulds; Tile Abrasion
Machines; Compacting Factor
Apparatus.

Full details on request.

CAPCO (SALES), LTD.

BEACONSFIELD ROAD, LONDON, N.W.18.

Telephone: WILLESDEN 0067-8.

Cables: CAPLINKO, LONDON

(Sole Agents for all
"Capco" Products)

Reinforced Concrete

DESIGN AND CONSTRUCTION

Floors

IN SITU AND PRECAST

Staircases

Cast Stone

Granolithic Pavings

Duromit Pavings

(In association with the Kleine Co. Ltd.)

STUART'S

GRANOLITHIC CO. LTD.

FOUNDED 1840

LONDON

105 Baker Street, W.1.

Telephone: Welbeck 2525/6.

BIRMINGHAM

Northcote Road, Stechford.

Telephone: Stechford 3631/2.

EDINBURGH


46 Duff Street.

Telephone: Edinburgh 61506.

MANCHESTER

Ashton Road, Bredbury, Stockport.

Telephone: Woodley 2677/8.



WATER TOWER FOR LEEK R.D.C., STAFFORDSHIRE
Consulting Engineers: Messrs. Willcox, Raikes and Marshall



**BUILDING AND
CIVIL ENGINEERING
CONTRACTORS**

BANNER CROSS HALL • SHEFFIELD 11 • TEL. 50016

A new outlook on buildings . . .



CHERRY ORCHARD FEVER HOSPITAL—CLONDALKIN. Architect: Alan Hope, Esq., B.Arch. A.R.I.B.A., A.M.T.P.I., 50 Merrion Square, Dublin, Eire. Contractors: Murphy Bros. (Dublin) Ltd., Castlewood Avenue, Dublin, Eire. "Sealantone" Liquid Colours for Cement incorporated in external renderings of this hospital. Various Colours used.

SEALANTONE LIQUID COLOURS

Combine scientifically with cement for colouring cement renderings or concrete floors. In many colours permanent and dustproof, actually improving the strength and general characteristics of all cement renderings, concrete floors, etc.

SEALANTEX LIQUID STONE COMPOUND

Revolutionary stone-like compound, in any colour for stone, asbestos, new or old concrete, brickwork, etc., externally or internally.

SEALOCRETE LIQUID STAIN

Imparts pleasant colourful effects to asbestos, brickwork, concrete, stonework, etc., maintaining and protecting the texture.

SEALOCRETE TEXTURED CEMENT PAINT

Needs only the addition of water for mixing. Applied to cement renderings, concrete, brickwork, etc., forms hard, durable coating with resistance to water penetration. Pastel shades.



SEALOCRETE PRODUCTS LIMITED

ATLANTIC WORKS, HYTHE RD., LONDON N.W.10

Telephone: LADBroke 0015-6-7


Grams and Cables: Sealocrete, Wesphone, London

Stand No. 44, The Ministry of Works Building Plant Exhibition, Reading, 24-30 June.

ONE...



TWO!



'STABIL' BINDERS

ARE GREAT LABOUR SAVERS

In one simple action they fix reinforcing rods as though welded. No slipping. No "fiddling" with wire. No tools to get mislaid. Any workman can use them. Made in all sizes for binding $\frac{1}{2}$ -inch up to $1\frac{1}{4}$ -inch rods. Give "Stabil" Binders a trial and judge for yourself.

- SEND TO-DAY for demonstration samples and prices.

HUNTLEY & SPARKS LTD

DE BURG RD., S. WIMBLEDON, S.W.19

Phone: Liberty 2446

REINFORCED CONCRETE CONSTRUCTION



HEAVY REINFORCED
CONCRETE RETAINING WALL IN
COURSE OF CONSTRUCTION



**UNITED KINGDOM CONSTRUCTION
& ENGINEERING COMPANY LTD..**

CIVIL ENGINEERING CONTRACTORS
HAMMOND ROAD, KIRKBY INDUSTRIAL ESTATE, LIVERPOOL.
TELEPHONE: SIMONSWOOD, 2607 (13 LINES)

it is cheaper to use your own
concrete testing equipment. . .

"MILBANK-WELLS" HYDRAULIC PRESS AND CUBE MOULDS

will enable you to do testing on the site—
with equipment that is easily handled—for a
capital outlay of less than £100 for 4-in.
cubes, and for less than £200 for 6-in. cubes.
Press and Moulds comply with B.S. 1881.
For full details, send to :

MILBANK FLOORS LTD.

PRESTRESSED CONCRETE CONSTRUCTION
RIVER HOUSE, EARLS COLNE, ESSEX.

'Phone: 410

Manufactured for us by Horner & Wells, Ltd., Engineers,
Chelmsford, Essex.



GUNITE SPECIALISTS

WM. MULCASTER & CO. (CONTRACTORS) LTD.

We invite inquiries for Gunite Linings and Renderings
for new or old structures of every kind in any part
of the country.

HASLINGTON

CREWE

Telephone: Crewe 2265-6.



Prestressed concrete sections made with Ciment Fondu and used in the construction of a tobacco factory at Bristol.
By courtesy of C. W. Glover & Partners

PRESTRESSED CONCRETE STRUCTURAL UNITS


Cast one day—in service the next

The advantages of Ciment Fondu are significant in the manufacture of prestressed concrete. Rapid hardening and the high structural strength obtained in only 6-8 hours after placing effect speedier production and lower overall manufacturing costs. Curing is required during only 24 hours instead of the several days usually needed. Steam curing is not only unnecessary but undesirable. Fewer tensioning machines are required and the tensioned wires can be cut within 24 hours of casting. Ciment Fondu also possesses high resistance to chemical action, as proved by its applications in connection with sulphates, sea water, marsh land, waste flue gases, etc., etc., and its use therefore gives protection to the prestressing wires.



Concrete Rock-Hard within one day

LAFARGE ALUMINOUS CEMENT CO. LTD., 73 Brook St., London, W.1. Tel.: MAYfair 8546



The
PC3 PUMPCRET
Mobile
CONCRETE PUMP



Specifications :

Two Sizes	P.C.3	P.C.4
Capacities per hour approx.	20-24 cub. yd.	8-10 cub. yd.
Range :		
Horizontal approx.	1,500 feet	1,250 feet
or Vertical approx.	135 feet	125 feet
Pipeline	6" i.d.	4½" i.d.
Power required :		
Electric or Diesel	45 h.p. to 60 h.p.	25 h.p. to 35 h.p.

CONCRETE BY PUMP AND PIPELINE

- ★ The latest and most efficient method of placing concrete for Hydro Electric Schemes, Tunnels, Power Stations, Cooling Towers, Subways, Silos, Canals, Piers, Viaducts, Reservoirs, Bridges, Runways, Foundations, Buildings, Pylons, Pipe Spinning and Lamp Columns.
- ★ Pumpable concrete must of necessity be good concrete.
- ★ Pumps and Mixing Plant can be located at the most convenient position within the pumping range.
- ★ The continuous output of the Pump at a constant speed governs the working of the whole concreting gang.
- ★ All "Pumpcret" surfaces in contact with concrete are renewable.
- ★ Pump supplied in stationary construction, alternatively fitted with bogie wheels or on pneumatic tyres.

EFFICIENT RECONDITIONING SERVICE

FOR SALE AND HIRE

PUMPCRET

THE REGISTERED TRADE MARK OF
THE CONCRETE PUMP COMPANY LIMITED

THE CONCRETE PUMP COMPANY LTD

4 STAFFORD TERRACE, LONDON, W.8

Telephone: Western 3546

Telegrams: Pumpcret, Kens, London

HILCON FLOOR & WALL SLABS



IN CONJUNCTION WITH

Presweld

REGD. TRADE MARK

Modular construction using Hilcon Floor and Wall Slabs together with Presweld Components effectively reduces building costs, and enables buildings of up to 5-story construction to be completed more speedily and economically. Illustrated literature will gladly be sent on request.

See our permanent display at the Building Centre.

HILLS LIMITED

(WEST BROMWICH)

ALBION ROAD, WEST BROMWICH, STAFFS.
LONDON: 125 HIGH HOLBORN, W.C.1.

TEL.: WEST BROMWICH 1025 (7 LINES)
TEL.: HOLBORN 8005/6

Branches at Birmingham, Bristol, Leeds, Manchester, Newcastle-on-Tyne, Glasgow and Belfast.



THE "JOHN BULL" CONCRETE BREAKER

NEW "B.A.L." TYPE.

INCREASED:—

PENETRATION, RELIABILITY, LIFE.

REDUCED:—

VIBRATION, NOISE AND WEAR.

THESE ARE THE SALIENT FEATURES
OF THE NEW CONCRETE BREAKER

★ ★ ★

REAVELL & CO., LTD.

RANELAGH WORKS, IPSWICH.

TELEGRAMS: "REAVELL, IPSWICH."

TELEPHONE: 2124

COPPER STRIPS

for expansion joints

All Reinforced Concrete Engineers recognise the advantages of using copper strips for sealing joints in concrete work. Copper is ductile, will not crack under repeated bending, is non-corrosive and is unaffected by wet concrete. We specialise in the supply of perforated copper strips of all required lengths and widths for expansion joints, and shall be pleased to submit prices against detailed specification.



ALEX J. CHEETHAM LTD.

MORTON STREET · FAILSWORTH · MANCHESTER

Telephone: FAILsworth 1115/6

DS14

WATES BUILD

Reinforced concrete Grain silos at Gainsborough, Lincs.

Next time a reinforced concrete structure is under discussion it's worth remembering that Wates have all the production resources, skilled labour and organisation, as well as that all-essential varied experience, needed to make a smooth job of any contract anywhere. The advisory services of Wates' Engineers, Architects and Surveyors are always available to anyone contemplating the use of reinforced concrete.

WATES LIMITED

Building and Civil Engineering Contractors

1258/1260 LONDON ROAD, S.W.16. PHONE: POLLARDS 5000
LONDON · NEW YORK · DUBLIN

MOULD OILS & COMPOUNDS

for every process of
concrete production

CONCREAM

This non-staining, smooth and easy working white mould oil can be used with confidence on all classes of in situ and precast concrete work where the use of a white mould oil is recommended.

VIBRAMOL

This non-staining and non-separating mould oil is made specially for use on steel shuttering and moulds where vibrators are used, and provides a good film which is not readily moved under vibration.

SPRAYMOL

This grade of mould oil has been specially produced for use with a spray gun. It can be used with great economy on all types of shuttering and moulds, and will not separate under pressure.

"P.S."

Experience has shown that the production of precast and in situ prestressed concrete needs a special mould compound, and in collaboration with leading prestressed specialists we have produced Grade "P.S." Mould Compound for this class of work.

"8.A."

This Mould Compound has been specially produced to satisfy the requirements of those engaged in the production of spun concrete products.

CONCREAM Regd.
VIBRAMOL Regd.
SPRAYMOL Regd.
"P.S." & "8.A."

**PRODUCTS OF THE
ORIGINAL MAKERS OF
CONCRETE MOULD OILS**

We specialise in the production of mould oils and compounds for concrete work of every kind, from mass concrete work to high-class architectural stone work, and have an unrivalled experience which enables us to give expert advice on all mould oil problems. We have a grade for every purpose, and will be pleased to submit full details, samples, and prices on request.

RICH^d HUMBLE & SON, LTD., COLUMBA OIL WORKS, LEEDS, 3

Telephone : 27155.

ESTABLISHED 1854.

Telegrams : "Columba, Leeds, 3."

RAPID METAL *Formwork*

**speeds the construction
of GLENDEVON DAM**

See how quickly, how easily, this steel shuttering is raised without dismantling. When the Dam (towering 150 ft. high and with a span of 1,200 ft.) is completed the shuttering will become immediately available for any other type of concrete construction. No wonder contractors standardise on Rapid Metal Formwork, the speedy, efficient, and adaptable system of steel shuttering.



Authority: The Fife County Council.

Contract: Glendevon Dam, Perthshire.

Main Contractors: Holland & Hannen and Cubitts
(Scotland) Ltd.

Consulting Engineers: J. and A. Leslie & Reid,
Edinburgh.

You can depend on

Patentees and Sole Manufacturers:

RAPID METAL DEVELOPMENTS LTD.

209 Walsall Road, Perry Barr, Birmingham, 22b. Tel: Birchfields 6021. London Office: 47 Victoria Street, S.W.1.
Tel: Abbey 4077. Glasgow Office: 20 Blythswood Street, Glasgow, C.2. Tel: City 6312. Liverpool Depot: Great
Briton Farm, Kirkby, Liverpool. Tel: Simons Wood 2482. South Wales Depot: Bridge Road, Waunarlwydd, Swansea.
Tel: Gowerton 3277. U.K. Patent Nos. 682,870 and 682,916. Protected by Patents in all principal Countries.

RAPID METAL *Formwork*

GUNITE AND CEMENTATION



GUNITE



Systematic repairs to structures
based on systematic diagnosis of
defects.

WHITLEY MORAN & CO. LTD.

Specialists in the Repair of Engineering Structures

5 OLD HALL STREET, LIVERPOOL.

Telephone: Central 7975



**PIN YOUR FAITH
TO THE TESTED
BRAND.**

THIS LABEL ON
EVERY BARREL
CARRIES WITH IT
FORTY YEARS'
EXPERIENCE OF
MANUFACTURE.

**NONE OTHER IS
"JUST AS GOOD"**

THE LEEDS OIL & GREASE CO.


Phone 22480

LEEDS, 10

"Grams: "Grease."

REINFORCED CONCRETE ROADS

ECONOMIC
EFFICIENT
ENDURING



McCall's
MATOBAR
Welded
FABRIC REINFORCEMENT

McCALL & COMPANY (SHEFFIELD) LIMITED
TEMPLEBOROUGH, SHEFFIELD, P.O. BOX 41, AND AT LONDON

**REINFORCED
CONCRETE
by**



Prestressed Bridge at Dorchester for Dorset C.C. J. J. Leeming, M.I.C.E., County Surveyor.


A. G. MANSELL & CO. LTD

CIVIL ENGINEERING AND BUILDING CONTRACTORS

BRIDGES - RIVER AND SEA DEFENCE WORKS - WATER TOWERS - BUNKERS
SILOS - INDUSTRIAL BUILDINGS - ROADS - FOUNDATIONS - AND PILING.

70 VICTORIA STREET, LONDON, S.W.1. Telephone: TATE GALLERY 0088

CONCRETE REINFORCEMENT



We carry large stocks of M.S. and High Tensile Steel, which can be supplied cut to lengths, hooked and bent in accordance with schedules, or in random stock lengths, from our Stock-holding Department.

We specialise in Large projects, for which our Designers are always at your service.

FOR ALL CONSTRUCTION PURPOSES

SOMMERFELDS LTD.
WELLINGTON • SHROPSHIRE • Tel.: Well. 1000
LONDON OFFICE: 167 VICTORIA ST. • TELEPHONE: VICTORIA 1000

CEMENTATION

To engineers and architects concerned with the rational design of foundations by the methods of soil mechanics, cementation offers a unique and economic means of improving the physical and mechanical properties of soils which enables increased intensity of loading to be sustained with safety.

In addition to its uses in the design of new foundations, cementation can be applied to existing works where insufficient exploration of the subsoil or other conditions have led to unexpected settlement of the structure.

BORED PILES

Cast *in situ* piles can be put down to great depth, with a minimum of headroom and very little vibration, with designed bearing capacity.

Our wide experience is at your disposal.




BENTLEY WORKS DONCASTER

Tel.: DON 54177-8-9

GLASCRETE for SHELL ROOFS

Shell roofs can be efficiently lighted by simply placing precast GLASCRETE panels on the shuttering and casting in monolithic with the roof, thus saving time and labour in trimming openings.

Panels are cast to the curve of the roof and anchor bars are left protruding from the frame for bonding to the roof slab.



Factory, London.

Architects: Messrs. Clifford Tee & Gale.

Telephone: CEN. 5866
(5 lines)

J. A. KING & Co. LTD.,
181, QUEEN VICTORIA ST., LONDON, E.C.4



Coated Macadam
Concrete Aggregates
Granite Chippings
Crushed & Screened
Rubble

**ROWLEY REGIS
GRANITE QUARRIES LTD.**

Springfields, Nr. Dudley, Worcs.
Phone: Blackheath (B'ham) 2021



•

This photograph illustrates the first portion of Kellogg House, Chandos Street, London, W.1. The reinforced concrete frame was carried out in our patent FRAMEWELD system.

•

ARCHITECTS:
Lionel H. Fewster & Partners

CONTRACTORS:
Leighton (Contractors) Ltd.

FRAMEWELD

Trade Mark

Patent No. 589066

is a real TIME and MONEY saver

•

A copy of the FRAMEWELD hand-book describing the system will be sent on application.

•

T.C.JONES & COMPANY LTD

REINFORCEMENT SPECIALISTS

WOOD LANE · LONDON W.12. Tel: SHEpherds Bush 2020

BUTE STREET, CARDIFF. Tel: Cardiff 28786 · TREORCHY, GLAMORGAN. Tel: Pentre 2381

5312/IR29

.... FOR
**ESSENTIAL
 PROTECTION**



Left:—
 OIL COOLED TRANS-
 FORMERS, No. 3 Area
 Sheffield. Photograph by
 courtesy of Yorkshire Elec-
 tricity Board.

EVODYNE



Above:—LIVERSAY WASHER AND ROTARY
 SCRUBBER—Rowley Regis Gas Works. Photo-
 graph by courtesy of West Midlands Gas Board.

**CHLORINATED
 RUBBER PAINTS** SHOULD ALWAYS BE USED

• EASY WORKING • ECONOMICAL • LASTING DURABILITY

EVODYNE PAINTS are far in advance of other chemical resistant paints, and their widespread use follows many years of research at the Evode Laboratories, Stafford, to develop fully the physical and chemical properties of chlorinated rubber in order to provide the highest practical degree of protection to iron, steel and wood against acids, alkalis, corrosive gases and salt water.

EVODYNE PAINTS can be applied with equal success to alkaline surfaces such as asbestos cement sheeting, concrete and plaster, without special primers.

In these conditions EVODYNE PAINTS should always be used in preference to paints produced on an oil and synthetic resin basis.



EVODE LIMITED GLOVER STREET STAFFORD

Telephone: 1590/1/2

Telegrams: Evode, Stafford

LONDON OFFICE: 1, VICTORIA STREET, LONDON, S.W.1. Telephone: Abbey 4622/3

Christiani & Nielsen Ltd.


CIVIL ENGINEERING CONTRACTORS

*Contractors for the New Northam Bridge
for Southampton Corporation*



Borough Engineer and Surveyor : F. L. WOOLDRIDGE, ESQ., M.I.C.E., M.I.MUN.E.

*Consulting Engineers : MESSRS. RENDEL, PALMER & TRITTON,
125 Victoria Street, London, S.W.1*



Placing 85 ft. long prestressed concrete beam, weighing approximately 38 tons



**ROMNEY HOUSE, TUFTON STREET, WESTMINSTER
LONDON S.W.1**

Tel. : ABBey 6614/7

Tel. Address : RECONCRET SOWEST

use the **A.B.** **SERVICE** for concrete work

SHUTTER PANELS

All sizes and types

ADJUSTABLE SHORES

for floor and beam support

ADJUSTABLE CENTRE FORMS

for floor support

SHUTTERLOCK WALING CLIPS

for bracing with scaffold tube and locking the panels together, eliminating nuts and bolts in shuttering. Tremendous saving in erecting and striking costs

COLUMN CLAMPS : BEAM CLAMPS

ROAD FORMS : TRENCH STRUTS

We also design and manufacture Steel Moulds for Floor Beams, Piles, Railway Sleepers and all other precast concrete products

Let us solve your problems

A. B. MOULD & CONSTRUCTION CO., LTD.

92 WHITEHORSE ROAD

CROYDON

SURREY

Telephone : Thornton Heath 4947.

Telegrams : Abmould, Croydon.

WORKS: VULCAN WAY, NEW ADDINGTON, SURREY



this is the
ALLAM
All-British
**HYDRAULIC
 BAR CROPPER**

CAPACITY

ONE 1½ in. dia. MILD STEEL
 or a Multiple of smaller bars

Details of this range, all types of concrete
 vibrators, and contractors' plant, sent on request

E · P · ALLAM & CO. LTD.

LONDON: 45 Great Peter Street, S.W.1. • Telephone: Abbey 6353 (5 lines)
 SCOTLAND: 39 Cavendish St., Glasgow, G.5. Tel.: South 0186. Works: Southend-on-Sea. Tel.: Eastwood 55243



WASHED
BALLAST, SAND, SHINGLE &
Crushed Aggregate for Reinforced Concrete.

WILLIAM BOYER & SONS, LTD.

DELIVERED DIRECT TO ANY
 CONTRACT BY MOTOR LORRY.

Quotations on Application.

Telephone: Paddington 2824 (3 lines).

Sand and Ballast Specialists,

**IRONGATE WHARF,
 PADDINGTON BASIN, W.**

MEMBERS OF B.S. & A.T.A.

BARS for REINFORCEMENT

BARS in sizes from ½ in. to 1½ in. Mild
 Steel 28/33 T.T. cut to lengths.

BARS bent to schedule.

BARS for prompt delivery to site at com-
 petitive prices.

Send your inquiries to

PASHLEY & TRICKETT · LTD.

STOKE STREET, SHEFFIELD, 9. Telephone: 41136-7. Telegrams: "PET" SHEFFIELD, 9.

No. 4 IN A SERIES SHOWING TECHNICAL DEVELOPMENTS IN CONCRETE CONSTRUCTION

BOTTLING HALL EXTENSION

THE BREWERY, READING

Prestressed concrete - the new economy in building



Sponsor: H. G. SIMMONDS LTD.,
READING.

Architect: R. E. J. SOUTHALL,
A.R.I.B.A., READING.

Designer: PRESTRESSED CON-
CRETE CO. LTD., LONDON,
S.W.1.

Contractors: VIBRATED CON-
CRETE CONSTRUCTION CO.
LTD., LONDON, S.W.1.

The main beams of this extension were pre-cast solid section units 22 ft. long by 20 in. deep, tapering in width from 13 in. at the top to 8 in. at the bottom. Secondary beams were 30 ft. span by 40 in. wide by 17 in. deep of hollow box section to be transversely pre-stressed after erection.

*The design aspect of this project and others are to be published in brochure form. Write and reserve your copy now.


Ever since prestressed concrete construction was first used in this country, designers, architects and civil engineers have specified "Wire by Johnsons". The reason is quality built up on early experimental work with those specialist designers who studied and worked in the Continental development of this new building technique.

Johnsons have a long record of "Firsts" including indented wire for greater bonding and coils of 8 ft. diameter, from which the wire pays out straight.

wire was essential—

Johnsons the choice!

Richard Johnson & Nephew Ltd., Manchester, 11

SISALKRAFTused where
the **BEST** is essential**SISALKRAFT**—stands up to the job

The long and growing list of County Councils, Municipal Bodies, Public Works Contractors, and Builders who use SISALKRAFT is indeed a confirmation that "Quality remains long after price is forgotten".

In the field of concrete construction the skill of the Civil Engineer and the Public Works Contractor is brought to full realization by the dependability of SISALKRAFT, both as a curing medium—and—equally important—as an underlay.

Write NOW for technical details and samples.

Don't 'make do'— you can Now have the BEST

USE
SISALKRAFT
TRADE MARK

Sole Distributors for British
Sisalkraft Ltd.

J.H. SANKEY & SON. LTD.



New Sewage Disposal Works,

Willington, Co. Durham.

Crook and Willington Urban District Council.

Sydney Hall, Esq., A.I.A.S., M.I.H.E.,

Engineer and Surveyor to the U.D.C.

Messrs. D. Balfour & Sons,

Caledonian Buildings, 145 Pilgrim Street,

Newcastle-on-Tyne, 1.

Consulting Engineers.

TARSLAG

LIMITED

BUILDING AND CIVIL ENGINEERING CONTRACTORS

WOLVERHAMPTON • STOCKTON-ON-TEES • ROTHERHAM

Thousands

of miles of

Flexcell

EXPANSION JOINT FILLER

Flexcell contains 70% of bitumen impregnated cane fibre.

Flexcell conforms to the Air Ministry Specification for Expansion Joint Filler.

Flexcell complies with the Specification of the American Association of State Highway Officials (A.A.S.H.O.).

* Manufactured Specially by Celotex Ltd.

There is only one Flexcell...

Flexcell non-extruding expansion joint filler is specified throughout the world by leading Engineers, Architects, Government departments and Local Authorities. Thousands of miles of joints in roads, runways, buildings and civil engineering projects have been filled with Flexcell, and sealed with Expandite sealing compounds. Flexcell is low in cost and pre-cut ready for use.

It is the unique joint filler:

Write for technical information to the Sole Concessionaires in the United Kingdom.

EXPANDITE
LIMITED

CHASE ROAD, LONDON,
N.W.10
TELEPHONE ELGAR 4321 (10 Lines)

**WATERTIGHT
LININGS
FOR
RESERVOIRS,
SWIMMING
BATHS, ETC.**



**LININGS
FOR
TUNNELS,
SEWERS,
TANKS.**

*Specialists in the Repair and Reconditioning of
Reinforced Concrete Structures, etc.*

THE

GUNITITE
CONSTRUCTION CO. LTD
WESTERN HOUSE, HITCHIN, HERTS.



A symbol of quality
materials, experienced
workmanship, expert
supervision, and excellent
service.

for all forms of
**PRECAST
CONCRETE**

We specialise in the production of Precast Concrete structural members to standard or special designs, also products for the Electrical Industry, Sports Ground Contractors, and Fencing Contractors, and shall be pleased to submit quotations for your requirements.

H.B. CONCRETE CO. LTD.

Head Office and Works: VICARAGE ROAD, EGHAM, SURREY. Telephone: Egham 3092

COMPREHENSIVE TECHNICAL BROCHURE




**For big savings
in concrete
formwork**

If concrete is your business you will find this latest Rawlplug Company publication of great value and interest. It is packed with practical, down-to-earth information on shuttering problems together with details of Rawlties, Rawloops and Rawlhangers. May we send you a copy? Apply on your letterheading, send business card or state trade or profession.



**THE WORLD'S LARGEST MANUFACTURERS
OF FIXING DEVICES**

THE RAWLPLUG COMPANY LIMITED, CROMWELL ROAD, LONDON, S.W.7



"Expamet" Expanded Steel used as a reinforcement to the concrete flooring in the gallery of the Library of Canterbury Cathedral.
ARCHITECTS: Messrs. Denman & Son, F.A.R.I.B.A., Brighton.
CONTRACTORS: Messrs. G. H. Denne & Son, Canterbury.

'Expamet' Expanded Steel used in reinforcement of the Library of Canterbury Cathedral

HERE you see a typical application of "Expamet" Expanded Steel — as a reinforcement for concrete. "Expamet" Expanded Steel is the unique reinforcement that affords the highest degree of grip and bond in concrete. The shape of the meshes also assists in "distribution" of point or concentrated loads, and in preventing cracking of concrete due to shrinkage and changes of temperature.

A 'tailor-made' reinforcement

This strong adaptable metal is produced in a very large number of standard sectional areas; the weight of fabric varying from 2 lbs. to over 30 lbs. per square yard. Sheets are supplied cut to size—thus eliminating waste and loss of time.

"Expamet" is indeed a 'tailor-made' reinforcement.

What's your problem?

We will gladly submit designs and estimates for the reinforcement of all forms of concrete construction. Let us know what applications for "Expamet" you have in mind. Literature and samples will be sent on application. Write or telephone.

Expamet


An Expanded Metal Product

THE EXPANDED METAL CO. LTD.

Burwood House, Caxton Street, London, S.W.1.
Telephone: ABBey 3933.

Stranton Works, West Hartlepool.
Telephone: Hartlepool 2194.

Also at: ABERDEEN • BELFAST • BIRMINGHAM • CAMBRIDGE • CARDIFF • DUBLIN • EXETER • GLASGOW • LEEDS • MANCHESTER



ANOTHER ANGLIAN PRESTRESSED PRODUCT

Prestressed concrete beams in use on the partly-completed road-over-rail bridge on the Great North Road at Stamford. This illustration shows one of several trunk road bridges at present under construction using "ANGLIAN" prestressed beams.

*Photograph by courtesy of
British Railways, Eastern
Region. Contractors :
Messrs. Wellerman
Bros. Ltd., Sheffield*

PYLONS

PILES

SHEET PILES

ROAD AND

RAIL BRIDGES

ROOF

AND

FLOOR

BEAMS



ANGLIAN BUILDING PRODUCTS LTD · LENWADE 15 · NORWICH · Tel. : Gt. Witchingham 291



"PRESTRESSED CONCRETE OVER TAMPA BAY"

16mm SOUND FILM IN COLOUR


To Secretaries and Honorary Secretaries of Engineering Associations and Architectural Societies interested in prestressed concrete construction.

800 ft. 16 mm. colour film, with sound commentary, prepared for the Preload Company of New York, is available on loan from McCalls Macalloy Ltd.

Shows the construction and placing of the Lee-McCall beams for the trestle spans.

Running time : 20 minutes.

Also "Leyton Marshes Culvert" 800 ft. with sound commentary.



• **MCALLS MACALLOY LTD** • P.O. BOX 41 • SHEFFIELD



New Sewage Purification Works for City of Peterborough

The illustration shows the new sewage purification works for the City of Peterborough in an advanced stage. The Sludge Digestion Tanks taking shape in the foreground are the final structures. The whole contract, which includes five acres of drying beds and a $1\frac{3}{4}$ mile Effluent Drain not shewn, is scheduled for completion in mid-1954. Interesting constructional problems are involved as the site is lower than the adjacent river, and the deepest tanks were excavated 25 ft. below the river level. More than 10,000 cubic yards of rock were removed from the excavations.

Now, as in the past . . .

CUBITTS

build for the future

ENGLAND • SCOTLAND • OVERSEAS

HOLLAND & HANNEN AND CUBITTS LIMITED

One Queen Anne's Gate Westminster SW1

C148


*what make of pump
would you choose...*

FOR



1 FEEDING CONCRETE MIXERS

2 SLUDGE AND SEWAGE PUMPING



4 JET DRILLING HOLES

FOR over 15 years the name Pegson has been associated with the best in pump design and performance. The accumulated experience gained over this period in practically every field is at your disposal. Pegson technical representatives are always available to advise you on the choice of pumps most suitable for the job you have in mind. Let us know your requirements, we will send you literature giving full details and arrange for a demonstration.

If it's a job for pumping—it's a job for—

PEGSON
Marlow
PUMPS

PEGSON LTD., COALVILLE, LEICESTERSHIRE

Tel. : Coalville 234

London Office: Iddesleigh House, Caxton St., S.W.1.
Tel. : Abbey 2373

Scottish Office: 7 Lister Road, Hillington Industrial Estate,
Glasgow. Tel. : Halfway 1800



3 GENERAL DE-WATERING DUTIES



1 Pegson-Marlow Multi-point self-priming 22 H.H., 27 H.H., 37 H.H. engine driven models.

2 Pegson-Marlow Diaphragm or Plunger Pumps.

3 Pegson-Marlow Multi-point self-priming low head engine driven models.

4 A wide range of Pegson-Marlow multi-point self-priming high head engine driven pumps.

Please write for leaflets and ask for demonstration.


STEELCONCRETE DESIGN & CONSTRUCTION CO.

Incorporated Structural Engineers

We invite enquiries for the Design and Supply of all types of Reinforcement for Concrete Structures. Specialising in Foundation Work, Retaining Walls, Structural Repairs, Prestressed and Ordinary Reinforced Structures.

81 THURLESTONE ROAD, LONDON, S.E.27

Telephone: Gipsy Hill 2451



Trent Gravels

10,000 tons per week

Washed & Crushed 1½ in. to ¾ in.


We are the leading suppliers of high-class concrete aggregates in the area shown above. Prompt deliveries guaranteed and keen competitive prices quoted. Send for samples and prices.

TRENT GRAVELS LTD

ATTENBOROUGH

NOTTS

Telephone: Beeston 54255.



"CONCRETE SERIES" BOOKS ON CONCRETE

For a complete catalogue giving prices in sterling and dollars, send a postcard to:

CONCRETE PUBLICATIONS, Ltd.
14 Dartmouth St., London, S.W.1

STEEL TRENCH SHEETING

(Regd. design
No. 850839)

**Prompt
Delivery**

For the temporary lining of trenches and foundations. *Prices and full particulars on application to:—*

**DORMAN LONG & CO. LTD., SHEET DEPT.
AYRTON WORKS, MIDDLESBROUGH**

London Office: Terminal House, 52 Grosvenor Gardens, S.W.1

DORMAN LONG


**CONCRETE
PROOFING
Co. LTD.**

**GUNITITE
SPECIALISTS**

Expert advice and schemes submitted for gunite work of every kind. Complete information on the various uses of gunite will be gladly sent on request.


96, Victoria Street, Westminster, S.W.1

Telephone:
VICTORIA 7877 and 6275



Concrete is one of man's
strongest shields against the
elements. Resisting challenges of
time and tide, it straddles the world,
shaping docks, sea walls, canals and
giant bridges. Concrete takes its character
from the cement on which it is based and
has become a

***symbol of
stability***



This symbol identifies the products of
THE CEMENT MARKETING COMPANY LTD.
selling organisation of The Associated Portland Cement Manufacturers Ltd.,
The British Portland Cement Manufacturers Ltd.,
Alpha Cement Ltd., Portland House, Tothill Street, London, S.W.1.
Suppliers of Blue Circle Portland Cement, "Ferrocrete," "417" Cement,
Sulphate Resisting Cement, "Snowcem" Cement Paint, Hydralime, etc.

BRITISH CEMENT IS THE CHEAPEST IN THE WORLD

CONCRETE AND CONSTRUCTIONAL ENGINEERING

INCLUDING PRESTRESSED CONCRETE

Volume XLIX, No. 6.

LONDON, JUNE, 1954.

EDITORIAL NOTES

The Quality of Concrete.

IN recent years much attention has been given to the production of concrete of uniform strength. The useful results of all this research have been small. Most investigators have concentrated on refinements of present methods of making concrete, and few attempts seem to have been made to eliminate some of the variables which occur between the quarry and the hardened concrete. These variables in the raw materials, the proportioning, the water content, the mixing, the unmixing between the mixer and the shuttering, the lack of consolidation or the further separation due to careless spading or vibrating, the curing process, and so on, are the reasons why we must have concrete with an average compressive strength of 3000 lb. per square inch, and a maximum very much higher, before it is safe to stress it to 1000 lb. per square inch. The elimination of some of the reasons why the permissible compressive strength can be such a small proportion of the average strength is much more important than mathematical exercises such as the statistical analyses of test results and suggestions that risks be taken by ignoring the lowest.

How little we have progressed in producing concrete of more uniform strength is shown in some of the papers read at a symposium on the design of concrete mixtures and the control of the quality of concrete held in London last month under the auspices of the Cement and Concrete Association. The suggestion that the problem of relating the required average compressive strength to a specified minimum strength requires a statistical approach, and that the engineer must decide what risk he will take of a cube strength being below the minimum, seems to be a policy of despair and a risky one at that. For example, in a dam now in course of construction a thousand cubic yards of concrete are being placed each day, and three test cubes are being made at intervals during the day of eight hours. The cube with the lowest strength might be merely a badly-made specimen and not at all representative of the concrete in the work, it might be that only one mixer-batch was of poor quality, or it might be that one-third of the concrete placed during the day, that is 330 cu. yd., was of inferior quality. In one paper a table is given showing that the deviation from the average strength of fifty specimens made under closely-controlled conditions was 12.2 per cent. when calculated as "standard deviation", but that the strength of three of the cubes was 23 per cent. below the average; this represents 6 per cent. of the concrete, and it seems risky to ignore so much concrete having a strength so much below

the so-called "standard deviation," and which may be in a part of the structure subjected to the greatest stress. In another paper it is suggested that in the case of concrete with an average strength up to 3000 lb. per square inch there is no need to make any investigation so long as the strength does not vary by more than 30 per cent. to 80 per cent. from the average, according to the amount of supervision. In the case of high-quality concrete with an average strength above 3000 lb. per square inch it is stated that investigation is advisable only if the strength varies by 1000 lb. per square inch from the average, which seems to mean that if the average is 3100 lb. per square inch a variation between 4100 lb. and 2100 lb. per square inch must be considered as normal. No doubt such variations are common experience, and this is the reason why it is safe to assume that concrete has a strength of perhaps about one-quarter of the strongest, one-third of the average, and one-half of the lowest test results, and an unknown proportion of the unknown strength of the concrete when it is in the structure.

It is doubtful if such variations of the strength of the concrete in one structure were greater twenty years ago than they are to-day. Refinements in existing methods of securing higher strengths and greater uniformity have been introduced in recent years, but the concrete in one part of a structure may still be less than half as strong as in other parts. Something more than new methods of interpreting tests results and refinements by laboratory workers is necessary to remedy or seriously improve this state of affairs. Methods of distributing concrete without barrows or chutes, of removing excess water before the concrete hardens, and of cementing together ungraded coarse aggregate with grout, are among the newer radical departures from the traditional methods of concreting, and it seems that only by radical new methods will greater uniformity be obtained. Experiments have shown that it is possible to make a cement that is proof against moisture and can be stored in the open without deterioration. Is it not much more worth while to try to produce a concrete that will set and harden without the addition of large quantities of water? Such a concrete would solve most of the problems, for most of the troubles of concrete are due to the presence of more water than is necessary for the chemical reaction of the cement.

The author of one of the papers has gone a useful step farther. He has discovered that, for the same proportion of cement to combined aggregate, the strength of the concrete is the same whatever the grading so long as the total surface area of the particles of aggregate in a given volume is the same. In the tests the aggregate was separated into seven different sizes, the largest passing a $\frac{3}{4}$ -in. sieve and the smallest retained on a No. 100 sieve. The first mixture contained aggregate of all seven sizes, the second material of the three smallest and two largest sizes, the third the two smallest and two largest sizes, and the last the smallest and largest sizes only. The average compressive strength of all these concretes was 3475 lb. per square inch at seven days with a greatest variation of 95 lb. per square inch; at 28 days the average strength was 4717 lb. per square inch and the great variation only 67 lb. per square inch. This discovery should be useful in districts where graded aggregates are difficult to obtain.

An important step forward are courses for supervisors of concrete starting this year at the City and Guilds of London Institute, and at Croydon, Cardiff, and Edinburgh, on the suggestion of the Reinforced Concrete Association. A list of papers presented to the symposium is on page 206.

Reinforced Concrete Arch Bridge in Brazil.

By E. HAROLD SIDWELL.

A BRIDGE (*Fig. 1*) across the Rio das Antas in the south of Brazil, which is believed to be the second largest reinforced concrete arch in the world, has recently been completed. The arch has a span of 180 metres (610 ft.); the longest arch in the world is Sandö bridge in Sweden, which has a span of 866 ft. The river is subject to very rapid rises following rain. One set of wooden falsework was swept away by flood, and was replaced up to deck level by lattice steel pillars supporting lattice girders on which was erected the wooden falsework for the arch ribs and the shuttering for the deck (*Figs. 2 and 3*). The steelwork was designed so that it could be dismantled and used for another bridge on a nearby site.

Specification NB—6 for road bridges and the loading for Class 1 roads and NB—2 for the calculation and construction of reinforced concrete bridges (see Appendix 1) were used in the design. The principal traffic is heavy lorries carrying




Fig. 1.—Arch of 610 ft. Span.

timber from pine forests in the neighbourhood. The two arch ribs are hollow in cross section, varying from 5 m. (16.4 ft.) in depth at the springings to 3 m. (9.84 ft.) at the crown. Their width is constant at 1.5 m. (4.93 ft.), and their centres are 8.7 m. (28.5 ft.) apart. A span of 180 m. (610 ft.) and a rise of 28 m. (92 ft.) above the springings give a rise-to-span ratio of 1 to 6.4. The ribs are of catenary shape and carry a dead load (their own weight and that of the deck and supporting members) of 4.2 tons per foot at the crown and 6.95 tons per foot at the springings. The supporting posts are 23.6 in. square and the horizontal bracing between the arch ribs is of K shape above the deck and in the form of a slab below the deck. Contraction joints are provided at the middle of the length of the deck and above the springings, where the supporting columns are duplicated and separated by 1.18 in. The ribs were designed for a temperature variation of 5 deg. C. from the normal, the bridge being at a latitude of about 30 deg. south. Shrinkage of the concrete was assumed to be equivalent to a fall in temperature of 15 deg. C.; the coefficient of contraction of reinforced concrete in Brazilian specifications is 10^{-5} per degree C. The viaducts at each end of the bridge consist of a series of in-situ frames as shown in *Fig. 4*. The




Fig. 2.—Steel Falsework.




Fig. 3.—Steel Falsework.

total length of the bridge and viaducts is 915 ft. The viaducts have slender members to produce structural stability with a pleasing appearance.

Economy in materials is very important in Brazil, and the details of a design are considered much more than in Britain. Concrete sections are probably more slender than anywhere else in the world. The calculations for the viaduct frames were compared with experiments on celluloid models at the Instituto Tecnologia at Porto Alegre. After construction, strains in the pillars were measured with Huggenberger gauges while the trestle was subjected to a lateral load. Agreement among the different methods was reported to be good; none of these, however, revealed an interesting vibration problem which occurred when the viaducts and their decks were completed. By standing and twisting one's body on the deck of the viaduct at the contraction joint one could easily cause oscillations of as much as $\frac{3}{4}$ in.; this was rectified by the provision of inverted V-shaped members as shown in Figs. 1 and 4. A crack occurred in one of the edge-beams supporting the deck of the viaduct. Opinions differed on whether the slight settlement of the foundation which caused this was due to occasional layers of soft decomposed rock in the excavation, or to the use of dynamite in excavating the foundations for the arch ribs; the latter opinion seemed to have more support.

Although the local aggregate was not as cubical as was desired it was used because it was available. The concrete had strengths of 3880 lb. per square inch at twenty-eight days, and 640 lb. of cement were used per cubic yard. Other quantities were—In the arch ribs: 2420 cu. yd. of concrete; 128 tons of steel. In the deck: 655 cu. yd. of concrete; 108 tons of steel. In the viaducts: 523 cu. yd. of concrete; 49.2 tons of steel. In the foundations of the arches: 1070 cu. yd. of concrete; 32.4 tons of steel. The cost was 16,147,000 cruzeiros, which is equal to £107,500 at the present rate of exchange or £215,000 at the free market rate when the bridge was commenced.

The engineer of the bridge was Dr. Antonio Alves de Noronha (whose chief designer was Sr. Leopoldo de Castro Moreira) in co-operation with Sr. Anthonio Froes and Sr. Solon Fonseca, Chief Engineer and Bridge Engineer respectively of Rio Grande do Sul—the State in which the bridge is built. The contractors were Messrs. Christiani & Nielsen. The writer was privileged to work in the office of Dr. Noronha at Rio de Janeiro for nearly a year.

APPENDIX I.

Brazilian Code NB—6 of 1950 specifies the live loads to be considered in the calculation of three classes of road bridges. The loads are composed of road rollers, lorries, and miscellaneous traffic. Details of the vehicles are given in Tables I and II.

TABLE I.—ROAD ROLLERS.

	Type A	Type B	Type C
Total weight (tons)	6.88	15.72	23.60
Weight (tons) of front roller	4.92	6.98	9.84
Weight (tons) of each rear wheel	0.98	4.42	6.88
Width of front roller (ft.)	3.28	3.28	3.28
Width of each rear wheel (in.)	3.94	15.75	19.68
Distance between front and rear axles (ft.)	9.84	9.84	9.84
Distance between centres of rear wheels (in.)	62.99	62.99	62.99




Fig. 4.—Details of Viaduct.

TABLE II.—LORRIES.

	Type A	Type B	Type C
Total weight (tons)	5.92	8.85	11.81
Weight on each front wheel (lb.)	1655	3310	4410
Weight on each rear wheel (lb.)	4970	6620	8820
Width of each front wheel (in.)	3.15	4.72	4.72
Width of each rear wheel (in.)	7.08	9.45	9.45
Distance between front and rear axles (ft.)	9.84	9.84	9.84
Distance between centres of rear wheels (in.)	62.99	62.99	62.99

The live load due to miscellaneous traffic is to be calculated as a uniformly-distributed load whose intensity is given as a function of the parameter g_0 . Arches or main beams are calculated as follows.

- (a) With less than 25 m. (82 ft.) of theoretical span kg. per sq. m. g_0 lb. per sq. ft. g_0
- (b) With span l between 25 m. and 125 m. (82 ft. and 410 ft.) $[g_0 - (l - 25)]$ $\left[4.88g_0 - \left(\frac{l}{3.28} - 25\right)\right]0.205$
- (c) With more than 125 m. (410 ft.) of theoretical span $g_0 - 100$ $[4.88g_0 - 100]0.205$
- (d) For the calculation of the other members g_0 g_0

It is permitted to ignore fractions of 10 kg. per square metre (2 lb. per square foot).

Miscellaneous traffic is assumed to be distributed on the footpaths and the part of road not occupied by vehicles. For this purpose the area occupied by a vehicle (roller or lorry) is assumed to be a rectangle 8.2 ft. wide and 19.69 ft. long with the centre over the longitudinal axis of the vehicle midway between the front and rear axles.

In calculating arches or main beams it is permissible to ignore the effect of the redistribution of loads caused by the secondary beams. In the case of arches or main beams of 98.43 ft. or more span it is permissible to substitute concentrated loads of vehicles (roller or lorry) of equal load but uniformly distributed over a rectangle 8.2 ft. wide by 19.69 ft. long.

Class 3.—The loads for Class 3 bridges consist of $g_0 = 82$ lb. per square foot for miscellaneous traffic, a roller of type A, and as many lorries of type A as there are lines of traffic, less one, all pointing in the direction of the traffic, and in the most unfavourable position for the calculation of each member, with the exceptions that there must not be more than one vehicle in each traffic line, nor must there be less than 8.2 ft. between the longitudinal axes of two vehicles. The calculations must also allow for one roller of type B in the most unfavourable position for the member under consideration, but pointing in the direction of the traffic.

Class 2.—The loads comprise $g_0 = 92.5$ lb. per square foot for miscellaneous traffic, a roller of type B, and as many lorries of type B as there are traffic lines, less one, placed as described for Class 3 bridges. The calculations must allow for a roller of type C placed as for Class 3 bridges.

Class 1.—The loads comprise $g_0 = 102.5$ lb. per square foot for miscellaneous traffic, a roller of type C, and as many lorries of type C as there are traffic lines, less one, and placed as described for Class 3 bridges.

Brazilian Code NB—2 of 1950 specifies the vertical impact factors for road bridges as follows.

Elements of the roadway (slabs, cross beams, longitudinal beams, struts, ties), 1.3.
Straight main beams : Spans up to 65.7 ft., 1.3 ; Spans greater than 230 ft., 1.0.
Arches : Spans up to 164 ft., 1.2 ; Spans greater than 230 ft., 1.0.

For intermediate spans the coefficients of impact may be obtained by linear interpolation.

Vertical impact is not considered in the cases of (a) The transformation of loads for the calculation of earth pressures; (b) Bearings, solid pillars, and foundations; (c) Footpaths.

Precast Concrete Bridges in Australia.

In a recent report by the Engineer of the Country Roads Board of the State of Victoria, Australia, reference is made to the increasing use of precast concrete for

road bridges. For spans between 4 ft. and 20 ft. U-type precast slabs are used, and for spans between 22 ft. 6 in. and 37 ft. 6 in. precast T-beams have been




Fig. 1.—Method of Erection of Precast Bridges.

designed with precast deck slabs of the type shown in Fig. 2.

The erection of the larger bridges is by means of a cableway (Fig. 1) the towers of which are made up of sections 15 ft. long, each comprising four mild steel

angles braced by steel bars welded to them. The heaviest weight to be lifted for any bridge is 4.3 tons for the cross-heads, and with the aid of the cableway three of these may be placed in four hours.




Fig. 2.—Details of Precast Concrete Bridges.

Book Reviews.

"Prestressed Concrete Design and Construction."

By F. Walley. (H.M. Stationery Office. Price 30s.)

In his preface the author states that this book is based on the experience in prestressed concrete of the Ministry of Works and on his conversations with other designers in prestressed concrete. In view of the recent publication of M. Guyon's book and of the existence of books of other pioneers of prestressed concrete it cannot be expected that this latest addition to the literature will add much to common knowledge. However, the book is well written and has good and clear illustrations. A chapter on the principles of prestressed concrete is followed by a chapter on the behaviour of prestressed concrete under load which includes tables giving the calculated and the actual loads causing failure; it is seen that the calculated loads agree very well with the actual loads. Other chapters deal with materials, losses of tensioning forces, descriptions of methods of prestressing, experimental work, and design problems. A useful feature is a tabulation of the constants and geometrical properties of various sections of beams.

"Concrete Farm Structures."

By A. M. Pennington. 150 pages. (London: Concrete Publications, Ltd. 1954. Price 12s. 2.80 dollars in North America.)

The author has for many years specialised in concrete farm structures and ancillary works, and this book is based on his own experience and methods. Most of the structures illustrated have been designed by him and built under his supervision, and most of the precast concrete products described have been made in his own works. The design and construction of most types of farm structures are dealt with, including cowhouses, dairies, stables, piggeries, liquid-manure pits, dung-pits, barns, implement sheds, grain drying and storage silos, roads, paving, cattle-grids, gates, water-troughs, and horticultural frames. The chapter on silage and silos for grass brings up to date the author's book on this subject which has been out of print for some years. The designs are in accordance with the latest British and American practice, and also with British Standards and the recommendations of the Ministry of Agriculture where these are applicable. Fully-detailed working drawings are given for all parts of the

structures dealt with, and recommended methods of making the precast products are described at length. The last chapter is on the planning of farms.

"Brücken in Stahlbeton." Vol. I. Platten- und Balkenbrücken.

By Carl Kersten. 8th edition. 1953. (Berlin: Wilhelm Ernst & Sohn. Price 19 D.M.)

This work contains all the information necessary for the design and construction of slab and girder bridges in reinforced concrete. New matter deals with methods of prestressing in bridge work, the use of precast members, and methods of ensuring rigidity when a reinforced concrete deck slab is supported by a steel girder bridge. An important feature of this book is the 725 clear illustrations of structural details. For bridge parapets which are important from an aesthetic aspect the author prefers the open-type steel construction so as to ensure that the elevation shall be as light and graceful as possible, and this principle is well illustrated by photographs. This is in contrast to the practice in this country where, primarily in order to protect the public using a bridge, solid parapets are employed (Waterloo Bridge, London, is a notable exception).

"Berechnungsgrundlagen für Bauten."

By Bernhard Wedler. (Berlin: Wilhelm Ernst & Sohn. 1953. Price 7.50 D.M.)

THE twenty-second edition includes the German standard specifications required for the design of buildings, data relating to the properties of materials, dead and imposed loads, pressures on foundations, masonry, timber construction, structural steel, sound insulation, ventilation and the protection of buildings against dampness, frost, and fire. Scaffolding, including many types of cradles, is also dealt with. Methods are described for the design of chimneys, grandstands, colliery headgear structures, steel towers for supporting the equipment used for oil extraction, masts for overhead electrical supply, cranes, and buildings subjected to mining subsidence. There is, however, no mention of the design of reinforced concrete structures.

"Verdichtungstechnik und Verdichtungsgeräte im ausländischen Erdbau."

By Heinz Fösch. (Berlin: Wilhelm Ernst & Sohn. 1953. Price 9.80 D.M.)

DESCRIBES the methods of soil compaction developed in France, Great Britain, and the U.S.A., and the plant employed for this purpose.

German Recommendations for Prestressed Concrete.

RECOMMENDATIONS for design and construction in prestressed concrete have been issued in Germany. The recommendations relate to complete prestressing with no tensile stress in the concrete and partial prestressing in which some tensile stress in the concrete is permitted. The required properties of the concrete and steel are given in Table I.

SECTIONAL AREAS.—In calculating stress due to load and the factor of safety against cracking, the area F_i and moment of inertia I_i are obtained by considering the section as a whole, reckoning the area of steel as $(m - 1)$ times its actual cross section. The area of steel must be sufficient to resist all the tensile forces. Poisson's ratio (the coefficient of transverse strain) may be assumed to be $\mu = \frac{1}{4}$.

CREEP AND SHRINKAGE.—Losses due to the creep of steel may be disregarded provided that the stress in the steel is less than the creep limit, or that strain

due to creep is prevented. The relationship between deformation (ϵ) and constant stress (σ) is given in Fig. 1; it is assumed that the deformation of the concrete due to creep is proportional to the stress and that the modulus of elasticity of the concrete E_c is constant; ϕ and α_K vary with time and tend towards their limiting values of ϕ_∞ and α_∞ after about four years. The values of these coefficients are given in Table II.

These coefficients are related to the strength of the concrete at the time of application of the forces producing creep, and are taken from Fig. 2 and Table I

for various ratios of $\frac{W}{W_\infty}$ which define the

strength, where W is the cube strength at the time of transfer and W_∞ is the strength at 4 years; W_∞ is considered to vary from 1.15 to 1.30 W_{28} (W_{28} is the strength at 28 days). Prior to these

TABLE I.—PROPERTIES OF STEEL AND CONCRETE.

	Steel (E_s) (lb. per sq. in.)	Concrete (lb. per sq. in.)			Modular ratio
Cube strength at 28 days	—	4280	6410	8550	—
Minimum strength at "transfer"	—	3420	5140	6850	—
Modulus of elasticity (E_c)	—	4,280,000	4,980,000	5,700,000	—
Hot-rolled wires and bars	30,000,000	7.0	6.0	5.3	$\frac{E_s}{E_c}$
Cold-rolled or drawn wires and strips	28,400,000	6.7	5.7	5.0	"
Stranded cables comprising 2 to 7 wires (cold drawn or rolled) having a pitch of not less than 10 times the diameter of the cable	25,600,000	6.0	5.1	4.5	"
All other types of steel according to test results	—	—	—	—	"

Notes.—Welding of steel is prohibited. Tolerance of tensioning force ± 5 per cent.

TABLE II.—COEFFICIENTS OF CREEP AND SHRINKAGE.

Position	Creep (ϕ_∞)	Shrinkage ($\epsilon_s \times 10^{-6}$)
In water	0.5K to 1K	0
In moist air	1.5K to 2K	10
In open air generally	2K to 3K	20
In dry air	2.5K to 4K	30

recommendations, the decrease in the prestress was assumed to vary from 19,900 lb. to 21,400 lb. per square inch.

DESIGN CALCULATIONS.—The maximum tensile stress in the member occurs before the prestress is applied. As this is a temporary condition, higher stresses are permissible as indicated in line 22 of Table III. After the application of the prestress, and before the full dead and live loads are applied, the maximum compressive stress




Fig. 1.—Relationship between Deformation and Constant Stress.

TABLE III.—PERMISSIBLE STRESSES.

Application	Strength of concrete at 28 days (lb. per square inch)		
	4280	6410	8550
CONCRETE.			
<i>Compressive—</i>			
In compressive area at design load*:			
1. Rectangular sections: Axial bending in one direction	1568	1990	2280
2. Tee-beams and hollow sections	1420	1850	2140
3. Direct compression	1140	1568	1850
In tensile area at design load:			
4. Rectangular sections: Axial bending in one direction	1990	2560	3000
5. Tee-beams and hollow sections	1850	2420	2840
6. Direct compression	1568	2060	2420
<i>Tensile—</i>			
Full prestress at design load:			
7. In compressive area before full loading*	428	541	641
In compressive and tensile areas after full loading:			
8. Generally	0	0	0
In some cases described in the code:			
9. Direct Tension	114	142	171
10. Axial bending in one direction	285	356	428
Partial prestress at design load:			
11. In compressive area before full loading	428	541	641
In compressive area at full load and in tensile area with reinforcement proportionately distributed:			
11a. Generally	0	0	0
12. Direct tension	171	214	256
13. Axial bending in one direction	428	541	641
In some cases described in the code:			
14. Direct tension	214	285	356
15. Axial bending in one direction	570	712	855
<i>Shearing—</i>			
Principal inclined tensile stresses at design load:			
16. Full prestress and shearing stress due to transverse force	114	128	142
17. Partial prestress and shearing stress	228	285	342
Principal inclined tensile stresses at breaking load:			
18. Shearing stress due to transverse force	455	570	685
19. In bending before shearing force is established	228	285	342
<i>Bond—</i>			
20. At design load	114	128	142
21. At breaking load	199	228	256
PRE-TENSIONED STEEL.			
22. During tensioning, $\leq 0.8\sigma_s$			
23. At design load, $\leq 0.75\sigma_s$ $\leq 0.55\sigma_B$			

Note.— σ_s = yield stress. σ_B = stress at failure. * The "design load" may be different at different stages in the construction. "Full load" includes live load, dead load, the effects of creep, shrinkage, etc.

occurs in the tensile area of the concrete and the maximum tensile stress in the compressive area. As this state is of short duration and is counteracted when




Fig. 2.—Coefficients of Creep and Shrinkage.

the live load is applied, higher stresses may be used in accordance with lines 4 to 7 and 11 of Table III. The maximum stress often occurs before the commencement of creep and shrinkage. After creep and shrinkage have taken place there occurs the most unfavourable combination of stresses. This results in minimum compressive stress and maximum tensile stress in the tensile area of the concrete, maximum compressive stress in the compressive area, and, in some circumstances, in the maximum stress in the member. In most cases this combination produces also the maximum shearing stress.

FACTORS OF SAFETY.—A factor of safety against cracking is mostly required. Under combined dead and live loads, tensile stresses in the tensile area of the concrete are not in general permitted.

TABLE IV.—PERMISSIBLE TENSILE STRESSES IN CONCRETE IN BRIDGES CARRYING NORMAL RAILWAY TRAFFIC.

Application	Strength of concrete at 28 days (lb. per square inch)		
	4280	6410	8550
<i>At full prestress—</i>			
1. In compressive area during construction	114	142	171
2. In compressive area with full dead load and in tensile area with all dead and live loads	0	0	0
In compressive area at full dead load and live loads and in tensile area with all dead and live loads and forces due to temperature variations, friction on bearings, etc. :			
3. Direct tension	114	142	171
4. In bending	214	285	356
<i>Partial prestress—</i>			
5. In compressive area during construction	114	142	171
With full dead load :			
6. In compressive area	0	0	0
In tensile area for all dead and live loads, with proportionate distribution of reinforcement :			
7. Direct tension	171	214	256
8. In bending in lower tensile area and in upper tensile area with sealing coat	356	428	498
In upper tensile area :			
9. With asphalt finish	285	356	428
10. Without asphalt finish	171	214	256
With full dead and live loads :			
11. In compressive area generally	171	214	256
In tensile area with all dead and live loads and forces due to temperature variations, friction on bearings, etc. :			
12. Direct tension	214	285	356
In bending :			
13. In lower tensile area generally and in upper tensile area with sealing coat	428	541	641
14. In upper tensile area with asphalt finish	356	428	541
15. Without asphalt finish	214	285	356

Certain exceptions are, however, allowed in bridges and other structures where additional or secondary loads are included (lines 3 and 4 of Table IV and lines 9 and 10 of Table III). Tensile stresses are permitted in the compressive area (lines 7, 9 and 10 of Table III and lines 1, 3, and 4 of Table IV). Calculation of the safe load must be based on the most unfavourable combination of loads comprising the prestressing force, creep, shrinkage, 1.75 times the sum of the dead and live loads, and temperature variations. A large factor of safety for concrete is required so that the working stress is limited to two-thirds of the stress causing failure.

MOMENT OF RESISTANCE.—To assess the total compressive strength in bending and the lever-arm of the internal forces for a section, a graphical method employing stress-strain curves is recommended. For rectangular or nearly rectangular sections the compressive force in the concrete may be assumed to be

$$D_c = 0.75 \times \frac{2}{3} \times W_{28} \times F_{bd} \\ = 0.5 \times W_{28} \cdot F_{bd},$$

where F_{bd} is the sectional area of the concrete in compression, $\frac{2}{3}$ is the reduction coefficient, and 0.75 is the coefficient to determine the area below the stress-strain curve as in Fig. 3. The distance of the point of application of the force representing the total concrete in compression measured from the compressed edge is 0.4 times the depth of the compressive area in bending.

SHEARING AND BOND STRESSES.—The magnitude and direction of the principal tensile stresses are determined from the shearing and compressive stresses. Where only compressive stresses are developed, the principal tensile stress in any part of the section must be calculated to find its maximum value; this is the case of full prestress (Fig. 4). If the stress distribution indicates compression and tension, the operative maximum value of the principal tensile stress is at or above the neutral axis within the concrete in compression; this is the case of limited or partial prestress (Fig. 5). In design load calculations, the principal tensile stress must not exceed the values in line 16 for full prestress and line 17 for partial prestress (Table III). In calculations for breaking load, the principal tensile stress must not exceed the values in lines 18 and 19 of Table III.




Fig. 3.—Stress in Relation to Strain.




Fig. 4.—Principal Stresses (Compression only).




Fig. 5.—Principal Stresses (Compression and tension).

Bond stresses need not be investigated where post-tensioned and untensioned steels are distributed nearly uniformly over the tensile area and the diameter of the mild steel bars does not exceed 1 in., and provided that the beam has sufficient anchorage. This rule also applies to members compressed with cables or stranded wires provided that the applied tensile force is less than 30 tons. For the design load the calculated bond stress is limited to the values in line 20 of Table III and for calculated breaking load by the values in line 21.

ANCHORAGE.—The force at the anchorage is assumed to be $\frac{1}{1.75}$ times the breaking load of the member.

In the case of pre-tensioned steel, the factor of safety of the bond must be ascertained by tests.

In the case of slipping between the steel and the anchorage, the steel may be further stretched, provided that the permissible stresses given in lines 22 and 23 of Table III are not exceeded by 5 per cent. in temporary over-stressing at the anchorages.

Thickened Slabs in Place of Beams.

THE Guelph General Hospital (*Fig. 1*), which has recently been completed in Toronto, has five stories and a basement, with a two-story penthouse on the roof containing machinery for the lifts and ventilation system. The building is in the shape of a letter L, one wing being about 208 ft. long by 46 ft. 6 in. wide and the other 102 ft. long by 48 ft. wide. The basement extends under the whole of the ground floor and projects 25 ft. 6 in. from the rear of the longer wing. The height of each story, floor to floor, is 11 ft. The structure comprises reinforced concrete

the floors are generally framed with beams, although not necessarily on all sides, and small openings may be made almost anywhere.

Each floor comprises a slab continuous over three spans across each wing; the central part, 10 in. thick, also spans longitudinally between strips with extra reinforcement between the two interior columns. The two outer spans are supported along the sides of the building by spandrel beams carried on columns. In the shorter wing these spans are 14 ft. 8½ in. and the slab is 5½ in. thick;




Fig. 1.—A Hospital with Beamless Floors.

slabs and columns with beams around the perimeter of the building only. The external walls are of brick and the internal partitions of hollow clay tiles.

This is one of the first buildings in Canada with wide bands of thickened slabs in place of beams. A plan of one of these beamless floors is shown in *Fig. 2* and a cross section in *Fig. 3*. It is stated that the advantages of this type of floor compared with beams and slabs are that the total thickness is reduced, that there is greater freedom for the arrangement of equipment, that fewer columns are required, and that the absence of beams allows a more flexible arrangement of internal walls. Large openings through

in the longer wing the spans are 12 ft. 10 in. and the thickness 4½ in. The increased thickness of the outer slabs near the columns was allowed for in calculating the bending moments.

Arrangement of Reinforcement.

The main reinforcement in the outer slabs comprises ½-in. bars at 6-in. centres, alternate bars being bent upwards into the central slab. In addition, in a lateral direction between the columns, there are at the top of the slabs three ½-in. bars at 9-in. centres, and at the bottom two ½-in. bars at 6-in. centres. These slabs are reinforced longitudinally with ½-in. bars at 1 ft. 4 in. centres to resist the effects




Fig. 2.—Plan of a Floor (The drawings do not show all the reinforcement).




Fig. 3.—Cross Section through Floors of Shorter Wing.

of shrinkage and changes of temperature, and with two $\frac{1}{2}$ -in. bars adjacent to the spandrel beams and four $\frac{3}{4}$ -in. bars near the central slab. The central slab generally has $\frac{1}{2}$ -in. bars laterally at 1-ft. centres in the top and bottom, lapping with the bars extending from the outer slabs, and $\frac{3}{4}$ -in. bars at 6-in. centres in the top and bottom for a width of 1 ft. 6 in. on each side of the centre of the columns. The longitudinal reinforcement consists generally of 44 bars of $\frac{3}{8}$ in. diameter, alternate bars being bent up over the lateral strips

previously mentioned. The reinforcement of a floor is shown in Fig. 2. The specified compressive strength of the concrete at 28 days was 3000 lb. per square inch and the allowable stress in the steel 20,000 lb. per square inch.

The architects are Messrs. Marrani & Morris, the structural engineer Mr. W. S. Glynn, and the contractors the Pigott Construction Co. The foregoing description is taken from an article by Mr. Glynn in the February, 1953, number of "The Engineering Journal" (Canada).

"Concrete and Constructional Engineering" Prize Design.

THE proprietors of "Concrete and Constructional Engineering" offer each year a prize of £25 for competition among the students of reinforced concrete technology at the City and Guilds College of the Imperial College of Science and Technology, London. Last year the subjects from which the students could select were a railway bridge over the river Thames, underground oil tanks, a building of 25 stories, an exhibition hall with a "shell" roof, a jetty, a conference hall, a car-park with a shell roof, a laboratory, an auditorium, a science centre, and an office building of seven stories. There were twenty entries. The prize was awarded to Mr. B. W. Cooper for his designs for a railway bridge and underground oil tanks. The subjects were set by Professor A. L. L. Baker, Professor of Concrete Technology, and the assessor was Mr. F. E. Wentworth-Sheilds, O.B.E., P.P.Inst.C.E. In his report the assessor states that the designs show that the students had mastered modern ideas in reinforced and prestressed concrete design and construction.




Fig. 3.—Front Elevation.




Fig. 2.—Plan.

Partially-prestressed Reinforced Concrete Helical Stairs.

RECENT extensions to Bologna University, for the Faculty of Chemical Agriculture, have partially-prestressed reinforced concrete stairs which are helical in shape and elliptical in plan (Fig. 1). The arrangement consists of a single curved beam which is fixed at the lower end in a foundation of trapezoidal shape and at the upper landing in a beam. The curved beam is of I section, the marble-faced stair treads being extended on each side to form the

tensile steel wires of 5 mm. diameter, in a metal tube; each cable was tensioned to 22 tons. The cables (Fig. 4) are arranged so that the resultant compression is central at the upper end and within the middle-third at mid-span; the load on the foundation is also within the middle third. Helical mild steel reinforcement is provided to resist torsional stresses, and mild steel reinforcement is used for the foundation and upper beam as shown in Fig. 4 (see page 198).




Fig. 1.

top flange. The height between floors is 19 ft. 8 in. and the width of the treads is about 4 ft. The width of all the treads is the same over the beam, but varies from one side to the other because the nosings are normal to the elliptical outline in plan. A plan is shown in Fig. 2 and an elevation in Fig. 3 (see page 196).

The superload was assumed to be $87\frac{1}{2}$ lb. per square foot and the maximum concrete stress 1000 lb. per square inch. The main beam is prestressed by two cables, each consisting of twelve high-

Under test loading, vertical deflections at mid-span of 0.45 mm. and 0.50 mm. on the internal and external faces were recorded and, assuming a modulus of elasticity of the concrete of 2×10^6 lb. per square inch, the stress was 284 lb. per square inch at the inner face and zero at the outer face. No permanent set remained after removal of the test load.

The architect was Sr. Luigi Riguzzi and the engineer Professor Giuseppe Rinaldi, chief engineer of the Corpo del Genio Civile of the Italian Ministry of Public Works.




Fig. 4.—Details of Helical Stairs (see page 197).

"Ritecure"

THE RIGHT CURE FOR CONCRETE

MEMBRANE CURING



Photograph by courtesy of Air Ministry.

26-in. thick Concrete Runway Construction. Contractors: Messrs. John Laing & Son, Ltd.

The contract illustrated above is one of many where "Ritecure" has proved its economical efficiency. The ease of application, drastic reduction of labour costs, and the assurance of complete curing, are only a few of the advantages gained by using "Ritecure" Membrane Curing Material. "Ritecure" is equally effective in hot or cold climates. One-coat application is sufficient. Covering down and/or wetting are eliminated.

Over 11,000,000 sq. yds. of concrete
cured in this country with "Ritecure"

For full details, write to:

STUART B. DICKENS, LTD.

36 VICTORIA STREET,

LONDON, S.W.1.

TELEPHONE: ABBEY 4930

WORKS: OLD MILTON STREET,

LEICESTER.

TELEPHONE: LEICESTER 20390

Handles pre-cast products to the manner born!

How delicately the Jones KL 44 Mobile Crane handles these 6-ft. diameter concrete pipes. Ease of control and precision alone commend the KL 44 to concrete products manufacturers. Add to these virtues its versatility and speed, and you have a very good crane. Compare the KL 44 — on price-for-capacity, design, specification, engineering, performance, and after-sales service.

EARLY DELIVERY

HIRE
PURCHASE
TERMS
CAN BE
ARRANGED



Jones Cranes are made in the following sizes :—
KL 15 for loads up to 15-cwt.
KL 22 for loads up to 2-tons.
KL 44 for loads up to 4-tons.
KL 66 for loads up to 6-tons.
KL 100 Rail Crane—for loads up to 6-tons. Will also shunt 200 tons.

JONES **KL44** MOBILE CRANES

Distributed in the United Kingdom by:

GEORGE COHEN SONS & CO. LTD. Wood Lane, London W12

Designed, manufactured and exported by their Associates:

K & L STEELFOUNDERS & ENGINEERS LTD. LETCHWORTH, HERTS.

THE
600
GROUP

545/1105

Strengthening the Foundations of the Guildhall, London.

THE work of reconstruction of the Guildhall, London, included underpinning and strengthening the buttresses of the north wall. This work is of special interest as an ingenious application of a new process was used to solve an oft-recurring problem. The Guildhall is 500 years old, and the buttresses consist of stone in the upper portions and, in some cases, of a conglomerate of chalk flints and broken

piles 28 ft. long on each side of each buttress and penetrating up to 8 ft. into the blue clay below, to cast a reinforced concrete beam (Fig. 1) on these piles against each side of the buttress and slightly undercut, bore holes through the buttress in line with holes cast in the beams, and then insert high-tensile wires, tension them, and subsequently pressure-grout them and so squeeze the buttress




Fig. 1.—Method of Prestressing Buttresses.

stone with lime mortar in the lowest portion. Each buttress weighs about 360 tons and will carry a load of about 60 tons from the arch rib in the roof. The new foundations are in a very restricted space and the hall is in constant use, and this, together with the friability of the materials at the base, the varying thicknesses and depths below ground of the walls, and the still different depths of the buttresses, presented an unusually difficult problem.

The method adopted was to sink bored

and transfer the load to the piles. In the first buttress treated the piles were tested with a pressure of 50 tons on each pair of piles, which was a little in excess of the design load, and no pile settled more than about $\frac{1}{8}$ in.


The work is described in detail in a paper by Mr. Burnard Geen, M.Inst.C.E., the engineer for the work, in the Proceedings of the Institution of Civil Engineers, March, 1954, where the method is summarised as follows. (a) It was not necessary to disturb the existing foundations

by excavating below them ; (b) it was not necessary during the process seriously to weaken the buttresses ; (c) the supporting beams were placed at various levels to

suit the varying levels of the existing foundations ; (d) when the operation on any buttress was completed it became immediately effective.

Patents Relating to Concrete.


Electrical Curing of Prestressed Concrete.



APPARATUS for moulding prestressed concrete articles such as poles, railway sleepers, etc., in which the steel is heated by electric current to accelerate the hardening of the concrete comprises (a) one or more moulds (1) with end flanges (9) to which are bolted end walls consisting of double slotted plates (7, 7'), one or both end walls being of insulating material or insulation (8) being interposed between one or both end walls and the flanges (9) ; (b) anchor plates (3, 3', 4, 4'), for holding the steel (2) after it has been tensioned ; and (c) means to insulate the moulds from their supports. The moulds may be on a roller track (11) and insulated therefrom by skids (12) strengthened with metal (13). The moulds may be arranged electrically in parallel paths or in series, as for example in Fig. 1 in which the leads (6, 6') for the electric current are taken to the adjacent ends of the steel of two lines of moulds, the other ends of the steel being connected


and the anchor-plates being insulated from earth and from each other.—No. 641,827. Metropolitan Vickers Electrical Co., Ltd. January 16, 1948.

Foundations.



IN order that a bed of silt (2) may carry structures such as breakwaters (20) it is consolidated and stabilized by reducing its water and air content. Pipes (4) are driven into the bed at intervals and within these pipes are tubes (5) whose entry may be facilitated by pumping water down the tubes to remove any silt which may have entered the pipe. A filter bed (11) is formed around the lower end of each tube by passing a mixture of sand and water down the tube or the pipe, and the pipe is then removed. When pipes are removed the tubes are connected to a header (12) leading to a suction system comprising a submerged pump (13) which has an outflow (14) to the surface, whilst the air is removed since a chamber (15) on the pump (13) is connected to a vacuum pump (17) at water level. The lower end of each tube may be fitted with a screen (19) provided with a valve that permits the escape of sand but closes on the application of suction so that only air and water can be drawn into the tubes. Sand may be added to the silt before the silt is de-watered and de-aerated.—No. 652,570. S. Akerib. October 13, 1948.

[Publication of British patents has been delayed due to the war.]



The illustration shows a Vibro rig in operation at Kilmarnock, Glasgow, where 1,050 Vibro cast-in-place reinforced concrete piles 18 in. in diameter were formed in lengths of approximately 30 ft. This work was carried out for Messrs. John Walker & Sons, Ltd. Consulting Engineers: Considère Constructions, Ltd., London. Contractors: Messrs. Melville, Dundas & Whitson, Ltd., Glasgow.

Vibro CONCRETE PILES

Every Vibro pile is treated as an individual unit in the foundation. It can never be too long or too short. It is formed to suit the ground at that particular spot and to carry its load with ample safety, yet without waste.

The Vibro system is designed on correct engineering principles that have been proved on innumerable contracts in all parts of the world.

A descriptive booklet will be sent free on request.



BRITISH STEEL PILING COMPANY LIMITED

KINGS HOUSE, 10 HAYMARKET, LONDON, S.W.1

Telephone: Trafalgar 1024/8


Telegrams: Pilingdom, Lesquare, London




SMITH'S

FIREPROOF FLOORS


The most adaptable System of
Suspended Hollow Concrete
Floor and Roof Construction
for large and small spans.



Showing uniform concrete soffit.
Obtained without use of slip tiles.



Showing Two-way Reinforce-
ment and Hollow Concrete
Blocks laid on Trianco Tele-
scopic Centers.



**2 WAY REINFORCED
SUSPENDED
CONCRETE FLOORS**

The Two-way Reinforced Floor for
distribution of point loads with
efficiency and economy, employing the
original system of steel Telescopic
Centers.

Midland Associated Company & Licensees,
**PARKFIELD CONCRETE PRODUCTS
COMPANY LIMITED,**
St. Peter's Road, NETHERTON,
Phone: Dudley 4315

SMITH'S FIREPROOF FLOORS LTD

IMBER COURT • EAST MOLESEY • SURREY

EMBerbrook 3300 (4 lines)

Corrosion of Steel in Prestressed Concrete.

MR. I. C. PARKINS, B.Sc., Ph.D., has sent the following note on tests made by him on the resistance to corrosion of steel in prestressed concrete.

Details of the specimens used are given in Fig. 1(a). The concrete was a 1 : 1½ : 3 mixture of high-alumina cement, river sand, and river gravel, with a water-cement ratio of about 0.4. The steel was pre-tensioned and was left protruding for about 1 in. at each end, and the specimens, which were 9 ft. 6 in. long, were loaded as shown in Fig. 1(b). The load was applied by tightening the nuts on the central clamp and one of the end clamps, and pulling the other ends of the specimens together by means of a screw attached to a link which was calibrated, using electrical resistance strain-gauges. When the required load was attained, the nuts on the free end-clamp were tightened until the load was removed from the link, leaving the ends of the two beams pulling against each other. Sixteen beams were cast and loaded in this manner. Four pairs were loaded to working load, that is no tension in the bottom considering the specimens to be acting as beams; the other four pairs were loaded to slightly over one-and-a-half times working load, when visible cracks appeared in the bottom. Four pairs were stored in the laboratory and the others were placed between high and low water in the river Tay; one position was in fairly clean swift-running water, and the other was in

TABLE I.

Specimen No.	Cube strength* (lb. per sq. in.)	Test load (lb.)	Test condition	Load at failure (lb.)
1	6920	660	River	2320
2	"	660	Laboratory	1980
3	7560	660	River	2240
4	"	660	Laboratory	2150
5	8230	1000	Laboratory	2150
6	"	1000	Laboratory	2320
7	8060	1000	River	2320
8	"	1000	River	2500

* At age of 24 hours.

more sluggish water which contained some sewage. The beams were left in these positions, alternately wetting and drying, for two years.

Twelve high-tensile steel wires of 0.079 in. diameter were used in each beam, and the final stress in the wires, after losses had occurred, was about 156,000 lb. per square inch. Therefore, with this wire, which had an ultimate stress of 310,000 lb. per square inch, corrosion had to penetrate to a depth of only just over one-hundredth of an inch for the stress in the wire to be increased to the ultimate stress.

Two pairs of specimens were destroyed when the part of the pier to which they were attached was damaged during a storm. The other specimens were subjected to a simple bending test to failure,




Fig. 1.

and the results are given in Table 1. It is seen that there was little difference in the ultimate strengths of the specimens, and none of the wires broke when the specimens failed. When the specimens were broken after testing the wires were still free from any sign of corrosion, although the wires that had protruded from the ends were completely eaten away.

This test suggests that prestressed concrete should be at least as resistant to cor-

rosion as reinforced concrete. In particular, the tests indicate that in the case of pre-tensioned steel, the danger of corrosion penetrating along the wires from the exposed or poorly-protected ends is not great provided that the concrete is of good quality.

The author is indebted to Professor W. T. Marshall for his interest in and supervision of this test, and to the Dundee Harbour authorities for the facilities to carry it out.

Plastic Moulds for Precast Slabs.

FOR the construction of a Naval Air Station at Miramar, California, U.S.A., many precast slabs, mostly 24 ft. long by 4 ft. wide, have been used. The slabs are $1\frac{1}{2}$ in. thick for roofs and $1\frac{1}{4}$ in. thick for floors. Along the sides are ribs 10 in. deep by $3\frac{1}{2}$ in. wide at the bottom increasing to $5\frac{1}{2}$ in. at the soffit of the slab; at 4-ft. centres there are transverse ribs $4\frac{1}{2}$ in. deep by 2 in. wide. The parts of the slab between the transverse and longitudinal ribs are designed as separate slabs spanning in two directions for an imposed load of 75 lb. per square foot. The reinforcement in the slab consists of high-tensile steel mesh bent downwards into the longitudinal and end ribs. Each longitudinal rib contains one deformed bar of $1\frac{3}{8}$ in. diameter near the bottom and a $\frac{1}{2}$ -in. bar near the top; each transverse rib contains one $\frac{1}{4}$ -in. deformed bar near the bottom. A floor slab is shown in Fig. 1. The concrete contained 750 lb. of cement per cubic yard and had a minimum crushing strength of 4000 lb. per square inch at 28 days; the working stress in compression was 1800 lb. per

square inch. To enable the slabs to be handled the day after casting, a crushing strength at 24 hours of at least 800 lb. per square inch was required.

The parts of the mould (Fig. 2) to form the soffits of the slabs and the sides of the ribs were made of a plastic material reinforced with a fabric of woven glass fibres. Each former was about 4 ft. square, extending the full width of the slab and to the centres of adjacent transverse ribs; six such formers were required for a slab 24 ft. long. These formers were made from wooden patterns. At the centre of each former was a hole for the attachment of a device to facilitate its removal.

The formers were arranged on wooden bases to enable slabs 24 ft. long to be cast, the edges of the slabs being formed by metal sides hinged to the bases (Fig. 3). The bases were carried on wooden frames at a convenient height for working. To the underside of the base were attached water-pipes and valves which were connected, by $\frac{1}{4}$ -in. pipes passing through the hole in the centre of each former,





Fig. 1.—A Floor Slab.



WIREWELD spreads the rolling load


In the concrete structure of Britain's new roads Wireweld steel fabric is proving its economy, meeting the high strength requirements with the

minimum of metal. Wireweld is helping to lighten the costs of road construction as it makes light of the rolling load of transport.



REINFORCEMENT LTD

LONDON: 43 UPPER GROSVENOR STREET, W.1. Telephone: GROsvenor 8101 & 1216 • BIRMINGHAM: ALMA STREET
SMETHWICK 40. Telephone: SMethwick 1991 • MANCHESTER: 7 OXFORD ROAD, MANCHESTER, 1. Telephone: ARdwick 1691
GLASGOW: 19 ST. VINCENT PLACE, GLASGOW, C.1. Telephone: City 6594



333 Simplex Cast-in-situ Concrete Piles were used in the foundations of the Municipal College Extensions in Anglesey Road, Portsmouth
Architect to the City of Portsmouth: F. Mellor, Esq., F.R.I.B.A.

Write for Illustrated Brochure

SIMPLEX CONCRETE PILES LTD.

25 BRECHIN PLACE,

SOUTH KENSINGTON,

LONDON, S.W.7

Telephone: Fremantle 0035-6

to rubber sheets $\frac{1}{8}$ in. thick by 10 in. square set in depressions of the same size in the formers. The rubber sheets were fastened to the moulds by waterproof tape.

To strip a mould, water was introduced between the rubber sheet and the mould and pressure maintained until the slab was free. The water depressed the centre of the plastic former under the rubber sheet and escaped into the space between the former and the slab. After about five minutes water could be seen leaking from the edges of the moulds and the slab could then be lifted.

The concrete did not bond to the plastic material which, after removal of the slab, was cleaned by compressed air and wiped with a damp cloth. The metal sides were oiled. After fifty uses there was no sign of deterioration of the moulds.

The slabs were lifted from the moulds by a crane with a device as shown in Fig. 5 and stacked ten high. Erection was by crane using the device shown in Fig. 5 or the cradle shown in Fig. 4.

The building was designed by Messrs. Kistner, Curtis & Wright, and the work described was carried out by the Trepte Construction Co. The foregoing is abstracted from an article by Mr. M. R. Montgomery and Mr. T. G. Atkinson in the Journal of the American Concrete Institute for May, 1953.




Fig. 2.—Section through Plastic Mould.




Fig. 3.—Mould for Slabs.




Fig. 4.—Cradle for Lifting Slabs.




Fig. 5.—Device for Lifting Slabs from Moulds.

Earth Pressure on Tunnel Lining.

An investigation to determine the pressure on a tunnel in London clay has been carried out by the Building Research Station in conjunction with the Metropolitan Water Board and is described in the Report of the Building Research Board.

The tunnel is 9 ft. diameter, with its axis 90 ft. below ground level, and is to convey water under a head of about 140 ft. The lining consists of plain precast concrete segments, 6 in. thick, of which ten form a ring of the lining and are jacked in position against the clay by tunnel shield jacks.

In order to determine the pressure of the clay on the wall of the tunnel gauges were cast in nine of the rings and the pressures measured over a period of about a year. The gauges, consisting of steel cylinders, measured the forces by means of the change in frequency of a vibrated wire anchored axially to the ends

of a cylinder. They were used in two ways, namely, (1) Set radially in the thickness of the concrete segments to bear on a floating steel plate placed flush with the external face of the concrete; twenty of the gauges were used in segments in three rings, and they measured the radial pressure of the clay on the lining. (2) Six pairs of gauges were placed circumferentially in split segments in four rings to measure the circumferential thrust.

As the segments were jacked into position the radial pressures and the circumferential thrusts rose immediately, then fell, and remained nearly constant. The radial pressures on the gauges around any one ring varied appreciably, but the average was about $2\frac{1}{2}$ tons per square foot, except in one ring near a substantial band of claystone rock where the average radial pressures were nearly 5 tons per square foot. The circumferential thrusts also corresponded to an average uniform

• SIEVE ANALYSIS



of

CONCRETE AGGREGATES



We specialise in the supply of single sieves and nests of sieves to B.S.410 for hand or machine sieving of concrete aggregates, test sieve vibrators, and cement testing gauze which will meet all the requirements of the Contractor and Builder for proportioning aggregates and testing cement. Send for full details.

ENDECOTTS (FILTERS) LTD.

251 KINGSTON ROAD

LONDON, S.W.19

Telephone: LIBerty 8121-2.

Telegrams: Endfilt, Wimbie, London



Some views of the open-air swimming pool at the Skegness Holiday Camp.
By kind permission of Messrs. Butlins Ltd.

★ waterproofing concrete with Sternson No. 300

Practical experience on a large number of water-containing structures has proved that STERNSON NO. 300 provides the most dependable means of obtaining a dense and impermeable concrete which will resist heavy water pressures. The list of important contracts on which STERNSON NO. 300 has been specified includes Swimming Pools, Factories, Harbour work, and underground structures of all types, and cement renderings on housing estates, etc. STERNSON NO. 300 is an integral waterproofer which can be used with confidence for all forms of concrete construction, and for providing a waterproof rendering for existing concrete and brick surfaces. STERNSON NO. 300 is a water repellent. It increases the tensile and crushing strengths without retarding the setting action. It increases the workability of the mix, thus permitting lower water-cement ratios. Full technical information on STERNSON NO. 300, and expert advice on all concrete waterproofing problems, are available on request.

STUART B. DICKENS, LTD.

36 VICTORIA STREET,

LONDON, S.W.1.

TELEPHONE: ABBEY 4930

WORKS: OLD MILTON STREET,

LEICESTER.

TELEPHONE: LEICESTER 20390

MISCELLANEOUS ADVERTISEMENTS.

Situations Wanted, 3d. a word : minimum, 7s. 6d. Situations Vacant, 4d. a word : minimum, 10s. Other miscellaneous advertisements, 4d. a word : 10s. minimum. Box number 1s. extra. The engagement of persons answering these advertisements is subject to the Notification of Vacancies Order, 1952.

Advertisements must reach this office by the 23rd of the month preceding publication.

SITUATIONS VACANT.

SITUATION VACANT. Qualified structural engineer experienced in reinforced concrete, preferably over 40 years of age and single, required for senior assistant position in Kenya. Write Box MR/172, c/o 95 Bishopsgate, London, E.C.2.

SITUATIONS VACANT. Structural engineering. Designers and draughtsmen required immediately in civil engineering department of The Coffee Co. (Great Britain) Ltd., 140 Piccadilly, London, W.1, for colliery structures and bunkers. Must be experienced in reinforced concrete and/or structural steelwork and also able to take off quantities. Pension scheme in operation. Write, giving age, experience, and salary required.

SITUATIONS VACANT. Company of reinforced concrete engineers and contractors have vacancies in their London office for experienced designers and designer-detailers. Write, giving full particulars of age, education, and previous experience, to Box C.C.538, c/o 191 Gresham House, London, E.C.2.

SITUATION VACANT. Reinforced concrete designer fully experienced for light framed structures and hollow tile construction. Pension scheme operating. Every alternate Saturday. Attractive salary. Holiday this year. Box 4038, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATIONS VACANT. THE BRITISH REINFORCED CONCRETE ENGINEERING CO., LTD., have vacancies for reinforced concrete designers and detailers, with experience, in their Stafford, London, Liverpool, Bristol, and Newcastle-on-Tyne offices. Staff pension scheme and five-days' week.

SITUATION VACANT. Designer-draughtsman required for London office of well-known reinforced concrete engineering contractors. Experience in reinforced concrete frames, floors, roof and staircase construction essential. Progressive post, pension scheme, alternate Saturdays. Write fully, stating salary required, to Box 323, ALLARDYCE PALMER, LTD., 109 Kingsway, London, W.C.2.

SITUATION VACANT. Opportunity for qualified senior structural engineer to join expanding Limited Company in London as design director. No investment required. Substantial earnings are assured to ambitious man with experience and ability to design reinforced concrete structures (in situ and precast) and foundations, and to build up an efficient design department. Please reply very fully, stating all details, otherwise the application cannot be considered. Strictest confidence observed. Present staff are aware of this advertisement. Box 4039, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATION VACANT. Experienced designer-draughtsman required with knowledge of reinforced concrete detailing. Work varied and interesting. Salary £450 to £550, according to ability. Applications, with full details of experience and when available, to REEMA CONSTRUCTION, LTD., Milford Manor, Salisbury, Wilts.

SITUATION VACANT. Cement and concrete engineer required to take charge of testing laboratories, London area. Good salary according to experience. Superannuation scheme. Housing in one year's time. Early applications, giving full details of experience, to Box P 759, 110 Old Broad Street, London, E.C.4.

Manchester Municipal College of Technology

Principal :

B. V. BOWDEN, M.A., Ph.D., M.I.E.E.

Head of Department of Building and Structural Engineering : W. B. McKAY, M.Sc.Tech., M.I.Struct.E.

FULL-TIME DIPLOMA COURSE IN STRUCTURAL ENGINEERING

This three years' full-time diploma course provides training for posts of responsibility in the industry and meets the requirements of the professional institutions.

The course has been submitted to the Institution of Civil Engineers and, subject to the Institution's approval, successful students in the diploma final examinations will be exempted from Final Parts I and II of the Institution Examination.

Applicants for admission must be 16 years of age or over, and must hold the General Certificate of Education with passes at the ordinary level in English, Mathematics and two Science subjects.

Session commences : October, 1954.

Prospectus and full particulars may be obtained from :

The Registrar, College of Technology, Manchester 1.

SITUATION VACANT. Draughtsman. THE STANTON IRONWORKS CO., LTD., near Nottingham, has a vacancy on its prestressed concrete plant for a mechanical draughtsman to prepare drawings and carry out minor design calculations for moulds and tackle. Some experience of prestressed or reinforced concrete would be an advantage but is not essential. The post is progressive and superannuated. Write in confidence with full details of qualifications to the STAFFING DIRECTOR.

SITUATION VACANT. Civil engineers interested in road construction required. Appointments will be, initially, at the company's central laboratory, where training will be given in soil mechanics, asphalt and concrete technology. Engineering degree or equivalent desirable. Write, stating age, qualifications and experience, to GEORGE WIMPEY & CO., LTD., Central Laboratory, Lancaster Road, Southall, Middlesex.

SITUATION VACANT. Structural engineer required for research and development work in reinforced concrete construction. Applicants must have university degree in civil engineering, or other recognised civil or structural engineering qualifications, and experience in structural testing, including use of strain gauges. Progressive position either as career in laboratory or by later transfer to other departments of the Wimpey organisation. Write to GEORGE WIMPEY & CO., LTD., Central Laboratory, Lancaster Road, Southall, Middlesex.

SITUATIONS VACANT. MINISTRY OF WORKS. Civil engineering assistants required for work on various sites. Candidates must be of British birth, and competent to check setting out with theodolite and level, or have knowledge of soil mechanics. Students who have passed Parts A and B of the A.M.I.C.E. examination will be considered, but, without this, some previous site experience is required. Although unestablished, these posts have long-term possibilities. Hostel accommodation available on sites. Salary range £420 to £640 per annum; starting pay up to £550 according to age and experience. State age, details of training, and experience, to W.G.10/C.W.E.3(G), MINISTRY OF WORKS, Abell House, John Islip Street, London, S.W.1.

(Continued on page 205.)

radial pressure of about $2\frac{1}{2}$ tons per square foot and suggested a variation in thrust around the rings. The axis of the tunnel was 90 ft. below ground level and the weight of the overlying saturated ground corresponded to a uniform radial pressure of about $5\frac{1}{2}$ tons per square foot, but water leaked freely into the tunnel and, if allowance were made for hydrostatic

uplift, the radial pressure would be only about $2\frac{1}{2}$ tons per square foot.

Measurements were also made, using a screw micrometer stick, of the change in diameter of the lining on five diameters on each ring incorporating load-measuring instruments. These observations showed a steady vertical flattening of the tunnel lining amounting to a few hundredths of an inch, a slight increase in horizontal diameter, and a slight decrease in total circumference.



The Training of Supervisors.

THE City and Guilds of London Institute has prepared for the 1954-1955 session a one-year part-time course in concrete practice which is intended to provide a qualification for supervisors and potential supervisors engaged in concrete work. The course comprises 24 lectures. Full particulars may be obtained (price 6d.) from the City and Guilds of London Institute, Department of Technology, 31 Brechin Place, London, S.W.7. Similar courses are to be held at Croydon, Cardiff, and Edinburgh.

MISCELLANEOUS ADVERTISEMENTS.

(Continued from page lit)

SITUATIONS VACANT. AIR MINISTRY WORKS DEPARTMENT requires in London structural engineer designer/draftsmen experienced in reinforced concrete or structural steelwork. Applicants should have sound technical training and several years of varied experience in design and detailing of (a) reinforced concrete construction for all types of buildings, or (b) steel-framed sheds, warehouses, and kindred types of buildings. Salaries up to £780 p.a.; starting pay dependent upon age, qualifications and experience. Extra duty allowance or overtime payable. Reasonable prospects of promotion. Posts temporary and non-pensionable but have long-term possibilities. Competitions held periodically to fill established vacancies. Applications from natural-born British subjects only, quoting A/E and stating age, qualifications and previous appointments, giving dates and stating type of work done, to AIR MINISTRY, S.2(h)/NA, Cornwall House, Stamford Street London, S.E.1.

SITUATIONS VACANT. Junior engineer and chemist (two positions) required as concrete technicians in an expanding progressive company manufacturing ready-mixed concrete in London, Midlands, and provinces. Good prospects for advancement to young men, preferably with some experience in specialised quality control, and prepared to continue their studies. Write READY MIXED CONCRETE, LTD., Readymix House, Dartmouth Street, London, S.W.1.

SITUATIONS VACANT. Consulting engineers require civil engineers for work in West Africa. Excellent opportunities for men with experience of structural design and all-round ability. Applicants should be single and not more than thirty-five years of age. Eighteen months' tour with three months' leave, kit allowance, passages paid, and generous bonus. Salaries £1,000 to £1,800, according to experience. Reply to Box 4040, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATION VACANT. Experienced reinforced concrete draughtsman required, Wallington-Carshalton area. Box 4041, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATION VACANT. North Eastern Gas Board, Civil Engineering Assistant. Applications are invited for the position of civil engineering assistant at the head office of the Board at Leeds. Candidates must have had experience in the design of reinforced concrete foundations and structures, and the preparation of drawings, quantities, and specifications. The salary will be within Grade APT.11 (£715 to £840 per annum) of the salary scales of the National Joint Council for Gas Staffs. The successful applicant will be required to pass a medical examination and participate in the Board's Staff Pensions Scheme. Applicants should complete the official application form which may be obtained from, and must be returned to, the CHIEF ENGINEER, NORTH EASTERN GAS BOARD, Bridge Street, Leeds, 2, within twelve days of the appearance of this advertisement.

SITUATION VACANT. Fully-qualified and experienced contractor's engineer for head office required immediately. Candidates must have experience in programming and of all kinds of falsework such as staging and cofferdams for civil engineering work. Apply in writing only, stating age, experience, and salary required, together with copies of any testimonials, to PETER LIND & CO., LTD., Romney House, Tufton Street, Westminster, S.W.1.

SITUATIONS VACANT. Structural steel designer-draftsmen and reinforced concrete detailers, experienced, required by consulting engineers. Pension scheme. Holiday this year. Five-days' week. Apply in writing, stating age, experience, and salary required, to HUSBAND & CO., 70 Victoria Street, London, S.W.1.

SITUATIONS VACANT. Several experienced reinforced concrete detailers required. Salary according to qualifications and experience. Staff canteen. Five-days' week. Apply "TWISTEL" REINFORCEMENT, LTD., Alma Street, Smethwick, Staffs.

(Continued on page 206)

The Quality of Concrete.

A SYMPOSIUM on "Mix Design and Quality Control of Concrete" was arranged by the Cement and Concrete Association and held in London on May 11 to 13 last. The following is a list of the papers presented.

Design of high-strength concrete mixes, by H. C. Ernroy and B. W. Shacklock; The design of concrete mixes on the basis of flexural strength, by P. J. F. Wright; Mix design and abrasion resistance of concrete, by C. L. a'Court; Mix design for frost resistance, by A. R. Collins, M.B.E.; Design of concrete mixes for compaction by surface vibrators, by R. H. H. Kirkham; The effect of the vacuum process on concrete mix design, by D. F. Orchard; Steam curing and its effect upon mix design, by A. G. A. Saul; A classification of natural sands and its use in mix design, by A. J. Newman and D. C. Teychenné; The control of concrete quality: a review of the present position,

by F. N. Sparkes; Method of achieving control of quality, by L. J. Murdock; Control of concrete quality on the small site, by J. H. Spanton; Quality control and its effect on structural design, by F. G. Thomas; Quality control for pre-cast concrete, by F. Cornelius, M.C.; Economic factors in the choice of aggregate grading in relation to quality control, by D. A. Stewart, M.B.E.; Quality control for road and airfield construction, by J. M. Fisher; Quality control for dams and mass concrete, by W. Dick; Ready-mixed concrete: quality control refinements, by L. Boyd Mercer; Some problems involved in destructive and non-destructive testing of concrete, by R. Jones and P. F. J. Wright; The application of statistics to concrete quality, by F. R. Himsworth; The problems of specifying and standardizing practice for concrete mix design and quality control, by A. R. Collins, M.B.E.

MISCELLANEOUS ADVERTISEMENTS.

(Continued from page 205.)

SITUATIONS VACANT. Designers and draughtsmen experienced in reinforced concrete and marine work required. Please apply, stating qualifications and experience, to CHRISTIANI & NIELSEN, LTD., Romney House, Tufton Street, S.W.1.

SITUATION VACANT. Reinforced concrete designer-estimator required for consulting engineer's office, Golder's Green. Five-days' week. Superannuation scheme. Canteen. Box 4042, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATION VACANT. Reinforced concrete detailer-draughtsman required for consulting engineer's office, Golder's Green. Five-days' week. Superannuation scheme. Box 4043, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATIONS VACANT. CLARKE, NICHOLLS & MARCEL, consulting engineers, require in their London office, for reinforced concrete work, designers and draughtsmen-detailers. Permanent positions. Good prospects. Apply in writing to 21 Westbourne Grove, London, W.2.

SITUATIONS VACANT. Reinforced concrete engineers have vacancies in their Bristol office for designers and detailers. Applicants for the former posts should have considerable experience in designing a variety of structures. For the latter posts neat draughtsmanship is essential and a knowledge of design would be an asset. Five-days' week. Salary dependent on experience and ability. Box 4046, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATION VACANT. Experienced draughtsman-detailer required for London office of consulting engineers. Good drawing-office experience in reinforced concrete work essential. Apply in writing, with full particulars of age, experience, and salary required, to RENDEL, PALMER & TRITTON, 125 Victoria Street, London, S.W.1.

SITUATION VACANT. Detailer with two to three years' experience required by consulting engineers in Harrow, Middlesex. Good salary and prospect of designing experience. Five-days' week. Write stating age, experi-

ence, and salary to Box 4045, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATIONS VACANT. Estimators. Simon-Carves, Ltd., have two vacancies for structural draughtsmen in one of their estimating sections. Working conditions are excellent and scope is good. D.O. bonus scheme and pension fund are in operation. Apply in writing, quoting reference (NS. 46), giving age and experience, to STAFF AND TRAINING DIVISION, SIMON-CARVES, LTD., Cheadle Heath, Stockport.

SITUATIONS VACANT. Ministry of Works has vacancies for assistant civil engineers for work on sites in Southern England. Candidates must be of British birth, have passed or gained recognised exemption from Sections A and B of the A.M.I.C.E. Examination, and have had experience of site construction work. Although unestablished, these posts have long-term possibilities and competitions are held to fill established posts. Hostel accommodation is available on sites. Salary range £638 to £988 per annum; starting pay up to £885 per annum according to age and experience. Application forms, quoting E 280/54/A, from M.L.N.S., TECHNICAL AND SCIENTIFIC REGISTER (K), 26 King Street, London, S.W.1.

SITUATION WANTED.

SITUATION WANTED. Qualified structural engineer desires change. Practical and competent designer-detailer, with considerable site and supervisory experience. Capable of taking complete charge of reinforced concrete or other structures from drawing board to completion. Would prefer semi-administrative appointment with specialist or civil engineering contractor. Age 34 and married. Car driver. Excellent references. Box 4044, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

FOR SALE.

FOR SALE. Steel panels for flooring. 3 ft. by 2 ft., and other sizes. Keen prices and delivery. E. STEPHENS & SON, LTD., Bath Street, London, E.C.1.

FOR HIRE.

FOR HIRE. Lattice steel erection masts (light and heavy), 30 ft. to 150 ft. high, for immediate hire. HELLMAN'S, Terminal House, London, S.W.1. Telephone: Sloane 5259.



for this

we've even

changed our name

Our name used to be Isteg Steel Products Ltd. For years that name has been associated with cold worked steel reinforcement bars of high quality. We were very proud of our Isteg twin twisted bar. But progress must have its way. Today, we have this new product—the Tentor Bar—acclaimed by structural engineers on the Continent and now manufactured exclusively by us. And our policy has always been to associate company and product as closely as possible. That is why we have changed our name to

The
TENTOR BAR
Company Limited

43, Upper Grosvenor Street, London, W.1
Telephone: GROsvenor 8101

* Full technical information is available in *The Tentor Bar Handbook*. Please send for one.

Tentor is manufactured by Guest Keen & Nettlefolds (South Wales) Ltd., Cardiff. McCall & Co. (Sheffield) Ltd., Templeborough, Sheffield. The United Steel Companies Ltd., Sheffield. The Tentor Bar Company Limited.

**STAFFORD**

Head Office
Tel: 444

BRC

DESIGN OFFICES

specialising in Reinforced Concrete work are strategically placed throughout the whole of the British Isles

**LONDON**


53 Grosvenor Street, W.1
Tel: Grosvenor 8371

**BRISTOL**


10 Orchard St., 1
Tel: 24455

GLASGOW

25 Newton Place
Charing Cross, C.3
Tel: Douglas 5906

**NEWCASTLE**


107 New Bridge St., 2
Tel: 28136

**LIVERPOOL**

Hepworth Chambers
Church Street
Tel: Royal 5375

**DUBLIN**

52 Fitzwilliam Sq.
Tel: 62039



BRC

*Specialists in
Reinforced Concrete
Design
and Suppliers of
Reinforcement*

THE BRITISH REINFORCED CONCRETE ENGINEERING CO. LTD., STAFFORD
London, Birmingham, Bristol, Leeds, Leicester, Liverpool, Manchester, Newcastle, Cardiff, Glasgow, Dublin, Belfast

M-W.723